

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Rice County Sec. 11 Twp. 20S Rge. (E) 7 (W)

Location as "NE/CNWSW" or footage from lines C SE NW
Lease Owner Anadarko Production Company & Diamond Shamrock Corporation

Lease Name Mc Intosh "A" Well No. #1

Office Address Box 351, Liberal, Kansas 67901

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 8-6-75 19

Application for plugging filed Verbal approval 19

Application for plugging approved " " 19

Plugging commenced 8-5 19 75

Plugging completed 8-6 19 75

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin

Producing formation Depth to top Bottom Total Depth of Well 3378 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				12-1/4"	266'	
				4-1/2"	3376'	2410'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mixed 25 sacks cement, pumped plug to 2800'. Cut off 4-1/2" casing @ 2410', pulled casing to 570'. Spotted 40 sacks cement @ 570', 15 sacks cement from 40'-0'.

RECEIVED
STATE CORPORATION COMMISSION

AUG 28 1975

CONSERVATION DIVISION
Wichita, Kansas

8-28-75

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pratt Well Service
Address 723 S. Ninnescah, Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Seward ss.
T. W. Williams


(employee of owner or owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. W. Williams, Division Office Supervisor
Box 351, Liberal, Kansas 67901

(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of August, 1975

My commission expires



Norma L. Atkinson

Notary Public.

KANSAS DRILLERS LOG


API No. 15 — 159 — 20,552 . 0000
 County Number

S. 11 T. 20S R. 7 W

Loc. C SE NW

County Rice

640 Acres
N



Locate well correctly
1699'

Elev.: Gr. _____

DF. _____ KB. _____

Operator
Anadarko Production Company & Diamond Shamrock Corporation

Address
Box 351, Liberal, Kansas 67901

Well No. 1 Lease Name Mc Intosh "A"

Footage Location
1980 feet from (N) (S) line 1980 feet from (E) (W) line

Principal Contractor Sterling Drilling Company Geologist _____

Spud Date 6-18-75 Total Depth 3378' P.B.T.D. _____

Date Completed 8-6-75 Oil Purchaser _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	266'	Common	275	3% CC
Production	7-7/8"	4-1/2"	10.5#	3376'	Pozmix	175	.5% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2 SPF		3340' - 3356'

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized w/2000 gallons 15% HCL + 30 ball sealers. Fraced	3340' - 3356'
w/20,000 gallons 1% geled KCL water + 20,000# 20-40 sand.	

RECEIVED
STATE CORPORATION COMMISSION

AUG 20 1975

INITIAL PRODUCTION

Date of first production _____	Producing method (flowing, pumping, gas lift, etc.) _____	CONSERVATION DIVISION Wichita, Kansas		
RATE OF PRODUCTION PER 24 HOURS _____	Oil _____ bbls.	Gas _____ MCF	Water _____ bbls.	Gas-oil ratio _____ CFPB
Disposition of gas (vented, used on lease or sold) _____			Producing interval (s) _____	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
Anadarko Production Company & Diamond Shamrock Corporation

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No.
1

Lease Name
Mc Intosh "A"

Dry Hole

S 11 T 20SR 7 ^{SE}_W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Shale-Clay	0	277		
Shale	277	1415		
Shale-Lime	1415	1565		
Shale	1565	2065		
Lime-Shale	2065	2438		
Shale	2438	2520		
Shale-Lime	2520	2990		
Lime	2990	3090		
Shale	3090	3160		
Shale-Lime	3160	3200		
Lime	3200	3265		
Shale	3265	3320		
Shale-Lime-Chert	3320	3371		
Kinderhook	3371	3378		
Total Depth		3378		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

T. W. Williams

T. W. Williams
Division Office Supervisor

Signature

Title

August 15, 1975

Date