


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plat

Rice County. Sec. 9 Twp. 20 Rge. 7 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C SW SWA

Lease Owner Templeton Energy, Inc.
Lease Name TOBIAS Well No. 1
Office Address 1212 Main St., Houston, Texas 77002
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole

Date Well completed 10/1 1981
Application for plugging filed 10/1 1981
Application for plugging approved 10/1 1981
Plugging commenced 10/1 1981
Plugging completed 10/1 1981
Reason for abandonment of well or producing formation
Dry Hole

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz
Producing formation Depth to top Bottom Total Depth of Well 3320'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	269'	8-5/8"	269'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

125 sks 50/50 poz., 2% gel, 3% cc.

60 sks @ 480'

40 sks @ 260'

10 sks @ 40'

10 sks in rathole

5 sks in waterwell

hole plugged @ 7:30 AM, 10/1/91

by Sun Cementing Co.

RECEIVED
STATE CORPORATION COMMISSION

OCT 13 1981

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allen Drilling Company

STATE OF KANSAS COUNTY OF BARTON, ss.

Gary Christopher (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

P.O. Box 1389, Great Bend, KS 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of October, 1981



My commission expires

Notary Public.

DRILLER'S WELL LOG

DATE COMMENCED: 09/25/81
DATE COMPLETED: 10/01/81

Templeton Energy, Inc.
TOBIAS Well No. 1
C SW SW
Sec. 9, Twp. 20S, Rge. 7W,
Rice County, Kansas.

ELEVATION: 1666' G.L.
1671' K.B.

FORMATION DATA:

2702 - 2747' Shale
2747 - 2847' Sand
2847 - 2884' Lime, shale
2884 - 3264' Lime
3264 - 3291' Chert, lime
3291 - 3320' Shale
3320' RTD

Heebner 2702'
Ireland sand 2747'
Brown lime 2847'
Lansing 2884'
Mississippi 3264'
Kinderhook 3291'
RTD 3320'

SURFACE DATA:

Ran 6 jts new 20# 8-5/8"
casing; tally: 262' Set
@ 269' w/ 225 sks 50/50
pos., 3% cc., Cemt. circ.,
plug down 11:30 PM, 9/25/81
By Howco

PLUGGING DATA:

125 sks 50/50 poz., 2% gel,
3% cc.: 60 sks @ 480'
40 sks @ 260'
10 sks @ 40'
10 sks in rathole
5 sks in waterwell
plug down 7:30 AM, 10/1/81
By Sun; J.H.Metz, plugger

A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON) ss.

RECEIVED
STATE CORPORATION COMMISSION

OCT 13 1981

Gary Christopher, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Gary Christopher

Subscribed and Sworn to before me this 7th day of October, 1981.



Ruth Brack
Notary Public