

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rice County, Sec. 9 Twp. 20S Rge. 7 (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE SE 1/4
Bennett & Gould

Lease Owner Bennett & Gould

Lease Name Tobias Well No. 1

Office Address 5828 North Broadway-Wichita, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hols

Date well completed February 11 19 56

Application for plugging filed February 11 19 56

Application for plugging approved February 11 19 56

Plugging commenced February 11 19 56

Plugging completed February 11 19 56

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3675 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	230	8 5/8	230	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Run half of drill pipe in hole. Gun pits to raise viscosity of mud.
Circulate heavy mud. Lay down rest of drill pipe. Build bridge of hulls at bottom of surface pipe. Run 15 sacks of cement through 7 joints of drill pipe. Fill hole with heavy mud to 18 feet. Run five sacks of cement to bottom of cellar.

Name of Plugging Contractor Salina Drilling Corporation, Inc. (If additional description is necessary, use BACK of this sheet)
Address 102 Insurance Building, Wichita, Kansas.

STATE OF Kansas COUNTY OF Saline, ss.
Loren W. Hallam (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Loren W. Hallam
Salina, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 11th day of February, 19 56

My commission expires 2-26-58

RECEIVED
STATE CORPORATION COMMISSION
WICHITA, KANSAS
MAR 27 1956
3-27-56
CONSERVATION DIVISION
WICHITA, KANSAS

PLUGGING
FILE SEC 9 T 22 R 72
BOOK PAGE 32 LINE 37

TOBIAS #1.

Elevation: 1685 D. F.

LEGAL DESCRIPTION: SE SE SE 1/4
Sec. 9, Twp. 20S., R. 7W., Rice Co.

Casing Record: 230' 8 5/8" Surface Pipe
with 200 sacks regular cement 2 1/2 cc

Operator: Bennett & Gould
5828 North Broadway,
Wichita, Kansas.

Contractor: Salina Drilling Corp., Inc.
102 Ins. Building,
Wichita, Kansas.

Well Commenced: 1-28-56

Geologist: Robert Frensley
102 Ins. Building,
Wichita, Kansas.

Well Completed: 2-11-56

Surface Soil and Sand	60
Shale and Shells	1010
Lime and Shale	1710
Lime	1850
Shale and Shells	2020
Lime and Shale	2610
Sandy Lime	2690
Lime	2755
Lime and Shale	2900
Lime	3260
Shale and Lime	3520
Shale, Sand, Lime	3595
Lime and Sand	3615
Sandy Shale	3638
Lime	3675

GEOLOGISTS TOPS

Heebner	2709
Brown Lime	2858
Lansing	2890
Base of E. G.	3165
Shale Conglomerate	3268
Cherty Conglomerate	3287
Kinderhook Shale	3294

Misner Sand	3521
Maquoketa	3529
Viola	3540
Simpson Dolomite	3569
Simpson Sand	3578
Arbuckle	3638

The above rotary log is true and correct to the best of my knowledge.

PLUGGING

FILE SEC 9 T 20 R 7W

BOOK PAGE 22 LINE 37

Loren A. Williams

Subscribed to and sworn this 11th day of February, 1956.

My com. expires 2-28-58

Loren M. Callough

Notary Public