

STATE OF KANSAS
STATE CORPORATION COMMISSION

**Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas**

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

**Strike out upper line
when reporting plug-
ging off formations.**

• NORTH

	10		
	7		

**Locate well correctly on above
Section Plat**

Name of Conservation Agent who supervised plugging of this well. Mr. Ruel E. Durkee

Producing formation. None Depth to top. _____ Bottom. _____ Total Depth of Well. 3321 Feet

Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

3321' to 3293' Filled up with crushed rock
3293' to 3274½' Filled up with 5 sacks of calseal
3274½' to 3270' Filled up with crushed rock
3270' to 3240' Filled up with 6 sacks of cement
3240' to 330' Filled with heavy drilling mud
330' to 325' Crushed rock bridge
325' to 280' Filled up with 15 sacks of cement
280' to 15' Heavy drilling mud and dirt bridge on top of the mud
15' to bottom of cellar Filled up with 5 sacks of cement



9-22-44

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Mr. S.K. Myers
Address P.O. Box 17, Great Bend, Kansas.

STATE OF Kansas, COUNTY OF Barton, ss.
Mr. Stanton K. Myers (employee of owner) or (owner or co-owner)

.....Mr. Stanton K. Myers..... (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Stanley K. Meyer 3 Sept.

P.O.Box 17, Great Bend, Kansas.

(Address)

SUBSCRIBED AND SWORN to before me this 21 day of September, 1944

My commission expires _____

Notary Public.

WELL RECORD

15.053.01348.0000

THE ATLANTIC REFINING COMPANY

830 Kennedy Building
Tulsa 3, Oklahoma

Block or Twp. 17S-10W

Lease PHELAN
Lease No KS-6630
County Ellsworth

Well No. 1

State Kansas

Location Center N/2 NE NW of
11-17S-10W

Elevation 1781 Feet

Drilled (Contract
Company ToolsContracted Depth
Completed DepthFeet (Started 6-2-44
Feet (Completed
Date (Deepened
(Cleaned Out

Name of Contractor Simpson & Noble, Inc.

Reached Total Depth 6-15-44

Contract Price Per Foot

Day Work

Well Estimated Cost
Well Actual Cost

Method of Drilling

BEFORE SHOOTINGAFTER SHOOTINGInitial Production
Settled ProductionFlowing
on PumpInitial Production
Settled ProductionFlowing
on Pump

Baume Test

Water With Oil %

Casing RecordTorpedo Record

SIZE	SET	PULLED	Date	Company	From	To	Feet	Size of Shell	Total Qts.
8 5/8"	333'	with 150 sacks							
5 1/2"	3272'	with 225 sacks							

FormationTopBottom

Shale and shells	0	210
Shells and sand	210	328
Blue and red shale	328	950
Shale and shells	950	1350
Broken lime and shale	1350	1615
Lime	1615	1753
Broken lime	1753	2250
Lime	2250	2343
Broken lime	2343	2599
Lime	2599	2776
Chert	2776	2786
Broken lime	2786	3000
Lime	3000	3239
Broken chert and shale	3239	3261
Conglomerate & Dolomite	3261	3278
Cherty Dolomite	3278	3282 TD

DEEPEMED:

Lime	3282	3321 TD
Filled up with crushed rock to	3293	
Filled up with 5 sacks Calseal to	3274	PBD

11 17 1000
124 11