

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 130 S. Market, Room 2078  
 Wichita, KS 67202

WELL PLUGGING RECORD  
 K.A.R.-62-3-117

API NUMBER 15-053-01008-00-01

LEASE NAME Frevert

WELL NUMBER #7

1650' Ft. from S Section Line

2970' Ft. from W Section Line

SEC. 11 TWP. 17 RGE. 10 (E) or (W)

COUNTY Ellsworth

Date Well Completed \_\_\_\_\_

Plugging Commenced 1/16/02

Plugging Completed 1/16/02

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR D.R. Lauck Oil Co., Inc.

ADDRESS 2215 S. Broadway, Suite 400, Wichita, KS 67202

PHONE (620) 263-8267 OPERATORS LICENSE NO. 5427

Character of Well SWD Docket #D23945

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ or about 1/16/02 (date)

by KCC per Melvin Urban / Virgil Clothier (Wit) (KCC District Agent's Name).

Is ACO-1 filed? Unknown If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top 3233' Bottom 3344' T.D. 3344'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0'	206'	10-3/4"	206'	0'
	Production	0'	3233'	5-1/2"	3233'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.  
Rigged up perforators. Shot holes at 3135', 1190', 938' and 260'. Ran tubing to 3135'. Spot 15 sx cement. Pulled to 1190', spot 35 sx cement with 150# hulls. Pulled to 938', spot 35 sx cement with 150# hulls. Pulled to 260', spot 50 sx cement. Pulled tubing out. Waited 1 hour. Filled casing up to top with 35 sx cement and 200# hulls. Mixed 30 sx cement at 300# max psi. Shut in at 200#.

Name of Plugging Contractor D.S. & W. Well Servicing, Inc. License No. 6901

Address P.O. Box 231, Claflin, KS 67525


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: D.R. Lauck Oil Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Joseph F. Strube (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Joseph F. Strube

(Address) P.O. Box 231, Claflin, KS 67525

 KAREN J. MITCHELL  
 Notary Public - State of Kansas  
 My Appt. Expires 4/13/02

SUBSCRIBED AND SWORN TO before me this 5th day of April, 2002

Karen J. Mitchell  
 Notary Public

My Commission Expires: April 13, 2002

RECEIVED  
 APR 08 2002  
 KCC WICHITA

OR