

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Ellsworth SEC. 11 TWP. 17s RGE. 10W E/W  
Location as in quarters or footage from lines:

SW/4


Locate Well  
correctly on above  
Section Platt.

Lease Owner D.R. Lauck Oil Company

Lease Name Freyvert #3 Well No. \_\_\_\_\_

Office Address Box 488 Ellinwood, Kansas 67426

Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_

Date Well Completed \_\_\_\_\_

Application for plugging filed \_\_\_\_\_

Plugging commenced 6-19-82

Plugging completed 6-29-82

Reason for abandonment of well or producing formation \_\_\_\_\_

Depleted

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3250'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				<del>8X8X8X</del>		
				10-3/4"	200'	none
				5-1/2"	3235'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

No Pipe Recovery: Pumped 60 sacks 50/50 pos, 4% gel, 3% cc down 10-3/4" surface pipe and pumped 3 sacks hulls and 190 sacks 50/50 pos, 4% gel, 3% cc down 5-1/2" casing. Dumped 3 yards ready-mix down long string and surface pipe to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 29 1982  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 347 Chase, Kansas 67524  
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of June, 19 82

Irene Hoover  
Notary Public.

My Commission expires:





D. R. LAUCK OIL COMPANY et.al.

Prevert #3

Sec. 11 T 17S R 10W Ellsworth County Kans

Commenced: June 11, 1948

Completed June 30, 1948

CASING: 10" 190' 175 sacks  
5" 3244 50 "

*E 1, 1799*

Soil & RR	70
RR & shale	163
RR	190
shale & shells	1605
broken lime	1740
lime	1820
lime & shale	1915
shale & shells	2180
shale & lime	2570
lime	2845
shale & lime	2900
lime	3233
Conglomerate	3240
lime	3244
Standardized	

Corrected Top Arbuckle	3244
Corrected Rotary	3248
Lime	3251
100' oil	
Lime	3256
400' oil	
lime	3259
lime	3266
Increase oil 650' oil	
Lime	3271
Increase oil 1050' oil	
Lime	3280
Increase Oil 1450 oil	
swab 10 bbls per hour	
for 3 hours	
Completed Est. 200 bbls	

Tops- derrick floor

Heebner	2800
Brown lime	2903
White lime	2931
Conglomerate	3234
Simpson	3243
Arbuckle	3244
Total Depth	3280