


FORM CP-4

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
P. O. BOX 17027  
WICHITA, KANSAS 67217

## WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plot

Ellsworth County, Sec. 11 Twp. 17 Rge. 10 (E) (W)  
Location as "NE/CNWSW" or footage from lines C SW NW SW  
Lease Owner D. R. Lauck Oil Co., Inc.  
Lease Name Frevert #8 Well No. \_\_\_\_\_  
Office Address Ellinwood, Kansas 67526  
Character of Well (completed as Oil, Gas or Dry Hole) oil well  
Date well completed September 1950 1950  
Application for plugging filed August 20, 1975  
Application for plugging approved August 21, 1975  
Plugging commenced 8/21/75 19\_\_\_\_  
Plugging completed 8/27/75 19\_\_\_\_  
Reason for abandonment of well or producing formation depleted.  
If a producing well is abandoned, date of last production July 1975  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman  
Producing formation Arbuckle Depth to top 3254 Bottom 3283 Total Depth of Well 3283 Feet  
Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

| FORMATION | CONTENT | FROM | TO   | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|------|--------|--------|------------|
| Arbuckle  | oil     | 3254 | 3283 | 10-3/4 | 203    | none       |
|           |         |      |      | 5 1/2" | 3254   | 1520'      |
|           |         |      |      |        |        |            |
|           |         |      |      |        |        |            |
|           |         |      |      |        |        |            |
|           |         |      |      |        |        |            |
|           |         |      |      |        |        |            |
|           |         |      |      |        |        |            |
|           |         |      |      |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole, ran sand to 3225', dumped 5 sacks cement.  
Shot pipe at 2508', 2410', 2020', 1822', 1626', 1528',  
worked pipe loose and pulled 47 joints. Pumped 5 sacks  
hulls, 30 sacks gel and 150 sacks cement. By Allied Cementing Co.  
PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 05 1975

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KELSO CASING PULLING  
Address CHASE, KANSAS  
Conservation Division  
Wichita, Kansas

STATE OF KANSAS COUNTY OF RICE ss.  
R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of August 1975

My commission expires



Notary Public.

D. R. Lauck Oil Company, Inc. et al

Frevert #8

Sec. 11-T17S-10W

Ellsworth County, Kansas

SW NW SW

Commenced: Aug. 31, 1950

Completed: Sept. 14, 1950

Casing: 10" 203' 145 sacks

5" 3254' 50 sacks

|                  |      |
|------------------|------|
| shale & red rock | 170  |
| sand             | 185  |
| red rock & sand  | 200  |
| iron             | 204  |
| shale & sand     | 560  |
| shale & shells   | 940  |
| salt & shale     | 1200 |
| shale & lime     | 2180 |
| shale            | 2250 |
| shale & lime     | 2580 |
| lime             | 2860 |
| lime & shale     | 2945 |
| lime             | 3250 |
| Conglomerate     | 3258 |
| Arbuckle         | 3261 |

Derrick floor

Arbuckle 3256

Rotary TD 3259

Corrected

Cable tools

Arbuckle 3254

Rotary TD 3257

Lime 3260 Rainbow

Lime 3262

Lime 3265½ free oil

Lime 3269½

Lime trace green 3272

Lime 3283

500 acid

est. 25 bbls

Tops- derrick floor

|              |      |
|--------------|------|
| Elevation    | 1804 |
| Heebner      | 2813 |
| Brown Lime   | 2914 |
| white lime   | 2941 |
| Conglomerate | 3246 |
| Arbuckle     | 3254 |

|             |      |
|-------------|------|
| Total depth | 3283 |
|-------------|------|

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 22 1975  
CONSERVATION DIVISION  
Wichita, Kansas