

15.053.19123.0000

Form CP-4
Rev. 12-15-80

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Ellsworth SEC. 11 TWP. 17S RGE. 10W E/W
Location as in quarters or footage from lines:

NE NE SE

Lease Owner Kelso Casing Pulling

Lease Name Peterman #4 Well No. _____

Office Address Box 176 Chase, Kansas 67524

Character of Well (Completed as Oil, Gas or Dry Hole): _____

Date Well Completed _____

Application for plugging filed _____

Plugging commenced 5-17-82

Plugging completed 5-22-82

Reason for abandonment of well or producing formation _____

Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation _____ Depth to top _____ bottom T.D. 3283'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	251'	none
				5-1/2"	3262'	1145'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom with sand to 3200' and ran 5 sacks cement. Shot casing @2416', pulled a total of 38 joints of 5-1/2" casing. Plugged well with 5 sacks hulls, 25 sacks gel, 8-5/8" plug, 130 sacks cement.

Plugging Complete.

RECEIVED
STATE CORPORATION COMMISSION
MAY 26 1982
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso

Box 176 Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of May, 1982



Irene Hoover
Notary Public.

My Commission expires: _____

RECEIVED
STATE CORPORATION COMMISSION

15 053 191231 0000

Phone 913-483-2627, Russell, Kansas
Phone 316-793-5861, Great Bend, Kansas

CONSERVATION DIVISION
Wichita Kansas

Phone Plainville 913-434-2812
Phone Kiowa 316-825-4618

ALLIED CEMENTING CO., INC. No 29789

Home Office P. O. Box 31

Russell, Kansas 67665

6/d

Date	Sec.	Twp.	Range	Called Out	On Location	Job Start	Finish
5-22-82	11	17S	10W	6:00 AM	8:15 AM		11:30 AM

Lease	Well No.	Location	County	State
Belknap	4	Hwy 4 + Hollywood Rd 4N	Ellsworth	KS

Contractor *Belknap*

Owner *KC 4N 17S*

Type Job *Old hole plug*

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cement and helper to assist owner or contractor to do work as listed.

Hole Size *12 1/4 - 7 1/8* T.D. *3283'*

Csg. Size *8 5/8 - 5 1/2* Depth

Charge To *Constat Oil & Gas Corp*

Tbg. Size Depth

Drill Pipe Depth

Tool Depth

Cement Left in Csg. Shoe Joint

Press Max. Minimum

Meas Line Displace

Perf.

EQUIPMENT

No	Cementer	Helper
154	<i>Kevin R</i>	<i>Mike D</i>
No	Cementer	Helper
No	Driver	
114	<i>0415</i>	
No	Driver	

CEMENT

Amount Ordered *130 cement 20 gal 5 Halls*

Consisting of

Common *130 @ 4.75*

Poz. Mix

Gel. *25 SF @ 6.25*

Chloride

Quickset

Halls 5 SF @ 14.00

Handling *160 @ .90*

Mileage *@ .66*

Sub Total

Total

Floating Equipment

DEPTH of Job

Reference:	Amount
<i>pop 1 1/2 csg</i>	<i>340.00</i>
<i>make @ 400</i>	
<i>8 3/8 plug</i>	<i>10.00</i>
Sub Total	
Tax	
Total	

Remarks: *5 Halls, 20 gal, 30 cement + 5 gal release plug 100 cement*

Dilbert Tomer State