

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15.135.00473.00.00

API NUMBER NA

LEASE NAME Frevele "A"

WELL NUMBER 2

660 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 22 TWP. 16 SRGE. 25 (X) or (W)

COUNTY Ness

Date Well Completed June, 1944

Plugging Commenced 11-13-85

Plugging Completed 11-13-85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Sohio Petroleum Company

ADDRESS 50 Penn Place, Suite 1100, Oklahoma City, OK 73118

PHONE# (405) 848-7571 OPERATORS LICENSE NO. 6854

Character of Well SWO

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, KS (witnessed by R. Lacy)

Is ACO-1 filed? No If not, is well log attached? No (Log sent with CP-1)

Producing Formation NA Depth to Top NA Bottom NA T.D. 4900'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From Surface	To	Size	Put in	Pulled out
			309	10-3/4"	309'	None
		"	4537	7"	4537'	"
		"	1698	5-1/2"	1698'	"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. RU Halliburton, Pump 150 BBLs gel down hole, lost circulation, pump 20 sks 60/40 poz with 1 sk hulls. Pull tubing to 2000'. Shut down wait 2 hrs. Pump 58 BBLs oil down hole, had circulation to surface. Followed gel with 50 sks 60/40 poz. Pull tubing to 1000' Pump 20 sks 60/40 poz. Pull tubing to 400' circulated hole with 60/40 poz. POOH with tubing. (Over)  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 5287

Address Box 428, Hays, KS 67601

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Gary Plisga, Sohio Petroleum  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Employee of Operator) or (Operator) of  
(Signature) Gary Plisga

(Address) 50 Penn Place, Suite 1100  
Oklahoma City, OK 73118

SUBSCRIBED AND SWORN TO before me this 25th day of Novem-er, 1985

Louise N. Skinner  
Notary Public

My Commission Expires: March 13, 1989

RECEIVED  
STATE CORPORATION COMMISSION

DEC 2 1985

Form CP-4  
Revised 08-84

Tie onto 10-3/4" Pump 1 sk 60/40 poz. Pressured up to 500# - hole full. RD - release Halliburton. RD - release Eagle Well Service. Well plugged and approved by State Inspector Richard Lacy.