

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ness County. Sec. 34 Twp. 16S Rge. 24 (E) (W) X

Location as "NE/CNW/SW" or footage from lines C NW SW

Lease Owner Barnett Oil Company

Lease Name Albers Well No. 1

Office Address 111 First National Building Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 11-26-63 19

Application for plugging approved 11-27-63 19


Plugging commenced 11-27-63 19

Plugging completed 12-6-63 19

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well PB 4500 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	216	None
				5 1/2	None	3619

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved in. Cleaned out cellar. Rigged up jacks.

Run bailer - 3 bbl of oil and water in hole up to 1600'. Sanded to 4480'.
Dumped 4 sacks of cement. Working pipe.

Working pipe. Shot pipe at 3630'. Circulating. Spotted 70 bbl of oil.

Working pipe.

Working pipe. Pulling pipe.

Pulling pipe. Mixing 20 sacks of mud and 20 sacks of cement. Pumped in at 600' and 20 sacks of cement at 180'. Build rock bridge at 110'. Capped well with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 11 1963

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas

CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10 day of December, 1963

My commission expires May 27, 1964

Notary Public.

BARNETT Oil Co.

411 First National Bank Bldg Wichita 2, Kan.

Lease ALBERS.

Well # 1

Location C. NW-SW, sec 34, T. 46S, R. 24W. Ness County,

P.T.D. 4523. 7 7/8" hole.

Casing 5 1/2" - 15 1/2" ss. set @ 45 1/4. 8 5/8" @ 216'. 125 say rirc.

Cement 125 say common. behind 5 1/2".

Plug Back 4500. (Lane wells cast iron Plug)

Perforations 23 holes @ 4493 to 4496.

Drillers Log. 0-35 Clay

35-65 Sand.

65-600 Shl.

600-770 Shly Red Bed.

770-890 Sand

890-1120 Shly Sand.

1120-1650 Shl + Red Bed.

1650-1865 Shl. + shells.

1865-1900 Anhydrite.

1900-2465 Shl. + shells.

2465-2715 Shl. + lime

2715-3210 Lime.

3210-3385 Lime + shale

3385-3478 Lime.

3478-3908 Lime + shale

3908-4269 Lime.

4269-4500 Lime + shale

4500-4523 Lime.

RECEIVED
STATE CORPORATION COMMISSION

DEC 2 1963

CONSERVATION DIVISION
Wichita, Kansas(Make Application)
(Reason)

Deane D. Shurpe