

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Ness County, Sec. 7 Twp. 16S Rge. 22 (E) W (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE SE
Lease Owner The Vickers Petroleum Co., Inc.
Lease Name Squier Well No. 1
Office Address 201 WKH Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 4 19 52
Application for plugging filed July 4 19 52
Application for plugging approved July 4 19 52
Plugging commenced July 4 19 52
Plugging completed July 4 19 52
Reason for abandonment of well or producing formation dry

NORTH

Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4597 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	220	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with mud to 210' Set plug at 210' dump 15 sx cement
Filled with mud to 35' set Plug and dumped 1/2 sack Hulls and 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JUL 12 1952
CONSERVATION DIVISION
WICHITA, KANSAS
7-12-52

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Jayhawk Drilling Co., Inc.
Address 201 WKH Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
John M. Little (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) John M. Little
201 WKH Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 8th day of July, 19 52
Allen J. Denton
Notary Public.

My commission expires August 13, 1953

PLUGGING
SIC 7-1 (6) 220
PAGE 20 LINE 41

THE VICKERS PETROLEUM CO., INC.

Squiggly Well #2
SE SE SE, Sec. 7-16S-22W
Ness County, Kansas

Casing Record
8 5/8" @ 220' w/ 150 sx.

Commenced: June 10, 1952
Completed: July 4, 1952

Elevation: 2439 R.B.
D & A

LOG

Surface, Lime & Sand	0- 100
Shale & Shells	100- 221
Shale, Shells & Sand	221- 975
Shale & Sand	975-1245
Sand	1245-1465
Shale, Sand & Red Beds	1465-1570
Red Beds, Shells and Sand	1570-1760
Red Beds, Shale & Shells	1760-1785
Anhydrite	1785-1830
Red Beds, Shale & Shells	1830-1905
Lime & Shale	1905-2230
Shale & Salt	2230-2400
Lime & Shale	2400-2580
Lime & Sandy Shale	2580-2690
Lime	2690-2705
Lime & Shale	2705-2780
Lime, Shale & Sand	2780-2835
Lime Broken	2835-2915
Lime & Shale	2915-3150
Shale & Lime	3150-3250
Lime & Shale	3250-3822
Shale, Black	3822-3824
Lime	3824-3830
Shale	3830-3842
Lime	3842-3854
Shale	3854-3859
Lime w/some Shale	3859-4132
Shale	4132-4144
Lime & Shale	4144-4232
Lime	4232-4302
Shale & Shells	4302-4311
Shale, Black	4311-4313
Shale & Lime	4313-4344
Sand	4344-4347
Shale & Lime	4347-4403
Sand	4403-4405
Chert	4405-4409
Chat	4409-4472
Dolomite & Shale	4472-4494
Dolomite & Lime	4494-4567
Cherty Dolomite	4567-4576
Dolomite	4576-4597 T.D.

SAMPLE TOPS

Drillers Anhydrite	1785 to 1830
Heebner	3822
Toronto	3842
Lansing	3859
Base Kansas City	4132
Marmaton	4144
Cherokee	4302-SSO-4313-27
Cherty Conglomerate	4405
Osage	4409
Arbuckle	4567

RECEIVED
CONSERVATION COMMISSION
JUL 12 1952
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this Log is true and correct to the best of my knowledge and belief.

THE VICKERS PETROLEUM CO., INC.

BY Lyle Thomas

Subscribed and sworn to before me this 11th day of July, 1952.

Allen P. Denton
Notary Public

My Commission expires August 13, 1953

PLUGGING
FILE SEC 7-16-22W
BOOK PAGE 24 41