

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NESS County. Sec 25 Twp. 16S Rge. XX 21 (W)

Location as "NE/CNW/SW" or footage from lines 150' W OF C NW SE

Lease Owner ALPINE OIL & ROYALTY CO., INC.

Lease Name AULT Well No. 1

Office Address 800 BITTING BUILDING, WICHITA, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed: 8-9 19 64

Application for plugging filed (PHONE 8-9-64) 8-14 19 64

Application for plugging approved (PHONE) 8-9 19 64


Plugging commenced 8-9 19 64

Plugging completed 8-9 19 64

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well ELDON PETTY

Producing formation Depth to top Bottom Total Depth of Well 4173 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
CLAY & SAND		0	70	8-5/8"	290'	NONE
SHALE & SAND		70	290			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

FILLED HOLE WITH HEAVY MUD TO 600 FEET. SET FIRST PLUG AT 600 FEET WITH 1/4 SACK HULLS AND 20 SACKS CEMENT. FILLED HOLE WITH HEAVY MUD TO 240 FEET. SET SECOND PLUG AT 240 FEET WITH 1/4 SACK HULLS AND 20 SACKS CEMENT. FILLED HOLE WITH HEAVY MUD TO 40 FEET. SET THIRD PLUG AT 40 FEET WITH 1/4 SACK HULLS AND 10 SACKS CEMENT. PLUGGED RAT HOLE WITH 2 SACKS CEMENT.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 17 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GABBERT-JONES INC.

Address 514 ORPHEUM BUILDING, WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. E. E. HALL (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. Hall

514 ORPHEUM BUILDING, WICHITA, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 14TH day of AUGUST 19 64

My commission expires OCTOBER 2, 1967

Vira A. McKenzie Notary Public.

GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS WELL LOG

R

AULT #1  
150' W OF C OF NW SE SECTION 25-16S-21W  
NESS COUNTY, KANSAS

COMMENCED: JULY 30, 1964  
COMPLETED: AUGUST 9, 1964

OPERATOR - ALPINE OIL & ROYALTY Co., Inc.

DEPTH		FORMATION	REMARKS
FROM	TO		
0	70	CLAY AND SAND	
70	290	SHALE & SAND	
290	960	SHALE	RAN 11 JOINTS 8-5/8" CASING, SET @ 290' W/ 180 SACKS CEMENT
960	1100	SAND	
1100	1160	SHALE & SHELLS	
1160	1610	RED BED - SHALE	
1610	1980	SHALE & SHELLS	
1980	2295	SHALE	
2295	2440	LIME - SHALE	
2440	2745	LIME	
2745	2915	LIME & SHALE	
2915	3135	LIME	
3135	3443	LIME - SHALE	
3443	3560	LIME	
3560	3665	LIME & SHALE	
3665	4173	LIME	
4173	TD		DRY & ABANDONED

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 17 1964  
CONSERVATION DIVISION  
Wichita, Kansas

I, E. E. HALL CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS LOG FOR THE WELL  
DRILLED IN 150' W OF C OF NW SE SECTION 25-16S-21W, NESS COUNTY, KANSAS, TO THE BEST OF  
MY KNOWLEDGE AND BELIEF.

E. E. Hall  
E. E. HALL

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE,  
ON THIS 14TH DAY OF AUGUST, 1964, PERSONALLY APPEARED E. E. HALL TO ME PERSONALLY KNOWN  
TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED  
TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND  
PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR  
LAST ABOVE WRITTEN.

V. A. McKenzie  
VIRA A. MCKENZIE, NOTARY PUBLIC

MY COMMISSION EXPIRES OCTOBER 2, 1967