


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Ness County, Sec 10 Twp 16 Rge (E) 21 (W)
Location as "NE/CNW/SW" or footage from lines C-SW NE
Lease Owner Pickrell Drilling Company
Lease Name Harms-Kendall "B" Well No. 1
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed September 20, 1967
Application for plugging filed September 20, 1967
Application for plugging approved September 20, 1967
Plugging commenced September 20, 1967
Plugging completed September 20, 1967
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4300 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	245'	None
RELEASED STATE CORPORATION COMMISSION OCT 13 1967						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 800'. Set plug. Cemented with 100 sacks.

Heavy mud to 240'. Set plug. Cemented with 25 sacks.

Heavy mud to 40'. Set plug. Cemented with 10 sacks to bottom of cellar. Plugged rat hole with 2 sacks cement.

(If additional description is necessary, use BACK of this sheet.)


Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.

C. W. Sebitts (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 Fourth National Bank Bldg., Wichita, Ks. 67202
(Address)

Subscribed and Sworn to before me this 26th day of September, 1967



My commission expires May 10, 1970

L. M. Whiting Notary Public.

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Bldg.
Wichita, Kansas 67202

Rotary Drilling Commenced 9-11-67

Rotary Drilling Completed 9-20-67

LOCATION: Harms-Kendall "B" No. 1
C. SW NE Section 10-16S-21W
Ness County, Kansas

CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

CASING RECORD: (13 jts.) 8 5/8" surface casing set at 245' and cemented with 150 sacks cement. Circulated. Complete 11:30 PM, September 11, 1967. No oil string was run. D. & A., plugged 9/20/67.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

110	Post Rock and Clay
244	Shale & Shells
245	Cement
930	Shale & Shells
1040	Shale & Red Beds
1310	Sand
1623	Shale & Shells
1668	Anhydrite
1810	Shale & Shells
2250	Shale
2665	Lime & Shale
2835	Lime
3770	Lime & Shale
4050	Lime
4120	Lime & Shale
4192	Lime
4210	Sand
4248	Shale & Sand
4300	Lime, Shale & Chert, RTD

C. F. S.
4182'
4192'
4206'
4225'
4245'
4248'
4280'
4300'

S. L. M.
Board 3623.21
Strap 3621.93
Diff. 1.28 No Corr.

Slope Tests
2500'
3000'
3500'
4000'

RECEIVED
STATE CORPORATION COMMISSION

OCT 13 1967

CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By [Signature]
C. W. Sebitts, Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 26th day of September, 19 67, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: May 10, 1970

[Signature]
Notary Public
L. M. Whiting