

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pawnee SEC. 5 TWP. 20 RGE. 16w E/W
Location as in quarters or footage from lines:
NE SW SW

Locate Well
correctly on above
Section Platt.

Lease Owner Murfin Drilling Co.
Lease Name Amquist #3 Well No. _____
Office Address P.O. Box 288, Russell, Ks. 67665
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 6/9/83
Plugging completed 6/9/83
Reason for abandonment of well or producing formation _____

Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
Producing formation _____ Depth to top _____ bottom T.D. 3840'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	1118'	none

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plug job only - No pipe recovery. Plugged well with 60/40 poz 2% gel 2% c.c.
and 2 sacks hulls down 8 5/8. (200 sacks)

Plugging complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of June, 19 83

My Commission expires:



RECEIVED Irene Hoover
STATE CORPORATION COMMISSION Notary Public.

JUN 16 1983

Sunray Oil Corporation
Tulsa, Oklahoma

Almquist Well No. 3

NE SW SW
Sec. 5-20S-16W
Pawnee County, Kansas

Contractor: The R. W. Rine Drilling Company
Started: 12-1-46 Finished: 12-14-46

LOG

Clay	0-	40	
Shale	40-	70	
Sand	70-	85	
Shale	85-	290	
Shale and shells	290-	440	
Shale and sand	440-	645	
Shale and shells	645-	730	
Red bed and shells	730-	1096	
Anhydrite	1096-	1118	8 5/8" csg. cemented @ 1118'
Anhydrite	1118-	1133	
Shale and shells	1133-	1350	
Lime and shale	1350-	1485	
Shale, shells and salt	1485-	1775	
Lime, salt and shale	1775-	1945	
Lime and shale	1945-	2210	
Sand, lime and shale	2210-	2345	
Lime and shale	2345-	3482	
Shale	3482-	3485	
Lime	3485-	3562	
Lime and shale.	3562-	3667	
Lime	3667-	3691	
Lime and shale	3691-	3775	
Conglomerate	3775-	3803	
Arbuckle lime	3803-	3826	
Lime and chert	3826-	3840	

TOTAL DEPTH: 3840'
Dry and abandoned

State of Kansas)
County of Barton) ^{ss}

I, Clyde W. Goddard, do hereby certify that the above is a true and complete log of the Almquist Well No. 3 located in the NE/4 of the SW/4 of the SW/4 of Sec. 5-20S-16W, Pawnee County, Kansas.

Clyde W. Goddard
Secretary

Sworn to and subscribed before me this 18th day of December, 1946.

Levitta Hancy
Notary Public

My Commission Expires July 1, 1950

RECEIVED
STATE CORPORATION COMMISSION

DEC 2 1982

CONSERVATION DIVISION
Wichita, Kansas