

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Pitting Building
Wichita, Kansas

OR

Strike out upper line
when reporting plugging
of formations.

~~FORMATION PLUGGING RECORD~~

Pawnee County. Sec. 5 Twp 20S Rge. 16W (E) (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines SW SW NE
Lease Owner Sunray Oil Corporation
Lease Name Charles Nelson Well No. 1
Office Address Box 195, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 2/22/47 19
Application for plugging filed 2/22/47 19
Application for plugging approved 2/22/47 19
Plugging commenced 2/22/47 19
Plugging completed 2/22/47 19
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production never 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well H. W. Kerr
Producing formation Depth to top Bottom Total Depth of Well 3796 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	Water	3778	3796	8 5/8"	1076'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Filled hole W/mud to 1060 spotted 20 sacks cement @ 1060. Filled hole W/mud and 15 sacks cement and mud to surface.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to F. H. Sabourin, Kansas Division Supt.
Address Sunray Oil Corporation, Box 195, Great Bend, Kansas.

STATE OF Kansas, COUNTY OF Barton, ss.
Louis T. Moffatt, employee (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Louis T. Moffatt
Sunray Oil Corp. Box 195 Great Bend, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of February, 1947

Viola Beck
Notary Public.

My commission expires My Commission Expires June 10, 1950

PLUGGING
FILE sec. 5, 20 p. 164
100 100 45 9

February 24, 1947

Sunray Oil Corporation
Tulsa, Oklahoma

Chas. Nelson #1

SW SW NE Sec. 5-20S-16W
Pawnee County, Kansas

CONTRACTOR: - Stickle Drilling Co.
Tulsa, Oklahoma

Started: February 7, 1947

Finished: February 23, 1947

LOG

Cellar	0 - 16	
Surface Sand & Shale	6 - 260	
Shale & Shells	260 - 470	
Sand	470 - 600	
Shale & Sand	600 - 720	
Shale & Shells	720 - 1025	
Red Bed	1025 - 1070	
Anhydrite	1070 - 1110	8 5/8" Csg. set at 1076'
Shale & Red Bed	1110 - 1450	475 sacks of cement
Shale Shells & Salt	1450 - 1630	
Shale & Shells	1630 - 2000	
Lime & Shale	2000 - 2385	
Lime	2385 - 2475	
Shale & Lime	2475 - 2945	
Broken Lime	2945 - 3105	
Lime & Shale	3105 - 3215	
Broken Lime	3215 - 3285	
Lime	3285 - 3743	
Conglomerate	3743 - 3760	
Lime	3760 - 3798	(Total Depth 3796 DF)

Plugged with 20 sacks at 1060 and 15 sacks at top.

State of Kansas)
County of Barton) SS

I, Fred E. Stickle, do hereby certify that the above is a true and complete log of Sunray Oil Corporation's #1 Chas. Nelson, located in SW Cor. SW/4 NE/4, Section 5- 20S - 16W, Pawnee County, Kansas.

(Signed) Fred E. Stickle

Sworn to and subscribed before me this 24th day of February, 1947.

My commission expires My Commission Expires June 10, 1950

Viola Beck

Notary Public

