

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pawnee SEC. 5 TWP. 20 RGE. 16w E/W
Location as in quarters or footage from lines:
SW SE SW

Locate Well
correctly on above
Section Platt.

Lease Owner Murfin Drilling Co. purchased by Kelso Casing Pulling
Lease Name Amquist #1 Well No. _____
Office Address Box 288, Russell, Ks. 67665
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 5/11/83
Plugging completed 6/9/83
Reason for abandonment of well or producing formation _____
Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
Producing formation _____ Depth to top _____ bottom T.D. 3813'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	1128'	none
				5 1/2"	3795'	1911'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged off bottom with sand to 3745' & ran 5 sacks cement. Shot pipe at
3015', 2800', 2504', 2317', 2129', & 1928'. Pulled total of 60 joints.
Plugged well with 3 hulls, 15 gel, 50 cement, 5 gel, 1 hull, plug, & 120
sacks cement.

Plugging complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of June, 19 83

My Commission expires:



Irene Hoover
RECEIVED
STATE CORPORATION COMMISSION Notary Public.

JUN 21 1983

September 17, 1946

Sunray Oil Corporation
 Philtower Building
 Tulsa, Oklahoma

Almquist #1

SE cor. SE/4 SW/4
 Sec. 5-20S-16W
 Pawnee County, Kansas

Contractor: Stickle Drilling Co., Tulsa, Oklahoma

Started: Sept. 1, 1946

Finished: Sept. 16, 1946

	<u>LOG</u>	Elevation: 2078' DF
Cellar	0 - 6	
Surface Shale & Sand	6 - 110	
Shale & shells	110 - 445	
Sand	445 - 605	
Sand & Shale	605 - 700	
Shale & Shells	700 - 740	
Sand	740 - 780	
Shale & shells	780 - 850	
Red Bed & Shale	850 - 1100	
Shells	1100 - 1123	
Anhydrite	1123 - 1146	Top Anhydrite 1123'
Shale & Lime	1146 - 1515	8 5/8" 32# SS Casing @ 1128'
Shale & Shells	1515 - 1845	475 Sacks Bulk Cement
Shale & Lime	1845 - 1990	
Broken Lime	1990 - 2135	
Lime & Shale	2135 - 2270	
Lime	2270 - 2325	
Shale & Lime	2325 - 2415	
Shale & Shells	2415 - 2545	
Shale	2545 - 2650	
Shale & Lime	2650 - 2840	
Shale	2840 - 2860	
Lime	2860 - 2880	
Lime & Shale	2880 - 3280	
Broken Lime	3280 - 3320	
Lime & Shale	3320 - 3368	
Lime	3368 - 3606	
Chery Lime	3606 - 3623	
Lime	3623 - 3796 T.D. (D.F. Rotary Meas.)	

5-1/2" 14# SS Casing set @ 3795' (D.F.) 150 Sx.

	<u>TOPS</u>	
Anhydrite	1123	
Rebner	3406 DF	
Lans. K.C.	3487 DF	
Base K.C.	3737 DF	
Sobuckle	3790 DF	
Total Depth	3796 DF	

State of Kansas {
 County of Barton { ss

I, Fred E. Stickle do hereby certify that the above is a true and complete log of Sunray Oil Corporation's #1 Almquist loc. in the SE cor. SE/4 SW/4, Sec. 5-20-16W Pawnee Co., Kansas

Fred E. Stickle

Sworn to and subscribed before me this 17th day of Sept., 1946

Viola Beck
 Notary Public

RECEIVED
 STATE COORDINATION COMMISSION
 DEC 2 1982
 CONSERVATION DIVISION
 Wichita, Kansas