

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pawnee SEC. 5 TWP. 20 RGE. 16w E/W
Location as in quarters or footage from lines:
SW

Locate Well
correctly on above
Section Platt.

Lease Owner Murfin Drilling Co.
Lease Name Amquist #2 Well No. _____
Office Address Box 288, Russell, Ks. 67665
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 6/9/83
Plugging completed 6/9/83
Reason for abandonment of well or producing formation _____

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
Producing formation _____ Depth to top _____ bottom T.D. 3778'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	1110'	none
				5 1/2"	3771'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug job only - No pipe recovery. Plugged well with 1 hull, 25 cement, 17 gel, 50 cement, 1 gel, plug, & 125 sacks cement down 5 1/2" casing.

Plugging complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of June, 1983



Irene Hoover
STATE CORPORATION COMMISSION Notary Public.

My Commission expires:

JUN 16 1983

Sunray Oil Corporation
Tulsa, Oklahoma

Almquist Well No. 2

NE SE SW
Sec. 5-20S-16W
Pawnee County, Kansas

Contractor: The R. W. Rine Drilling Company
Started: 11-6-46 Finished: 11-21-46

LOG

Clay and sand	0- 165	
Shale and shells	165- 420	
Shale	420- 490	
Sand	490- 630	
Shale	630- 635	
Shale and shells	635-1100	
Anhydrite Lime	1100-1110	8 5/8" csg. cemented @ 1110'
Shale and shells	1110-1920	
Lime and shale	1920-3444	
Lime	3444-3610	
Lime and shale	3610-3742	
Shale	3742-3773	
Lime	3773-3778	5 1/2" csg. cemented @ 3772'

54ft TOTAL DEPTH: 3778'

500'	inclination	0°	2250'	inclination	1°
1000'	"	0°	2400'	"	1°
1500'	"	0°	2500'	"	1°
2000'	"	1°	3000'	"	1°
			3250'	"	1°
			3500'	"	1°

State of Kansas)
County of Barton) ss

I, Clyde W. Goddard, do hereby certify that the above is a true and accurate log of the Almquist well No. 2 located in the NE/4 of the SE/4 of the SW/4 of Sec. 5-20S-16W in Pawnee County, Kansas.

Clyde W. Goddard
Secretary

Sworn to and subscribed before me this third day of December, 1946.

Louise Hancy
Notary Public

My Commission Expires Dec 31, 1947

RECEIVED
STATE CONSERVATION COMMISSION
DEC 2 1946
CONSERVATION DIVISION
Wichita, Kansas