

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pawnee SEC. 5 TWP. 20 RGE. 16w E/W (1)
Location as in quarters or footage from lines:
NE NE SW

Locate Well
correctly on above
Section Platt.

Lease Owner Murfin Drilling Company purchased by Kelso Casing Pulling
Lease Name Amquist #4 Well No. _____
Office Address Box 288, Russell, Kansas 67665
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 5/4/83
Plugging completed 6/9/83
Reason for abandonment of well or producing formation _____

Depleted
Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
Producing formation _____ Depth to top _____ bottom _____ T.D. 3746'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	1070'	none
				5 1/2"	3734'	717.80'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom with sand to 3680' & ran 5 sacks cement. Shot pipe off at 638'. Pulled total of 23 joints. Plugged well with 50 cement, 10 gel, plug, & 150 sacks cement.

Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Kansas 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of June, 19 83

My Commission expires:



Irene Hoover
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

JUN 21 1983

15.145.00720.0000

January 23, 1947

Sunray Oil Corporation
Tulsa, Oklahoma

Almquist #4

NE NE SW
Sec. 5 - 20S- 16W
Pawnee County, Kansas

Contractor: Stickle Drilling Co.
Tulsa, Oklahoma

Started: January 9, 1947

Finished: January 21, 1947

LOG

Cellar	0	-	6	
Surface Shale	6	-	110	
Shale & Shells	110	-	450	
Sand	450	-	600	
Shale & Shells	600	-	1030	
Shale	1030	-	1055	
Anhydrite	1055	-	1095	8-5/8" Csg. set at 1070'
Shale & Shells	1095	-	1450	480 Sacks Cement
Shale & Salt	1450	-	1860	
Shale & Shells	1860	-	2050	
Broken Lime	2050	-	2170	
Lime	2170	-	2370	
Lime & Shale	2370	-	2440	
Shale & Shells	2440	-	2525	
Lime & Shale	2525	-	2785	
Shale & Shells	2785	-	2890	
Broken Lime	2890	-	2965	
Shale & Lime	2965	-	3045	
Lime	3045	-	3270	
Lime & Shale	3270	-	3355	
Lime	3355	-	3559	
Lime & Shale	3559	-	3690	
Lime	3690	-	3735	(Total Depth Derrick Floor)

5 1/2" Casing set at 3734 DF and cemented with 150 sacks cement

State of Kansas {
County of Barton {ss

I, Fred E. Stickle, do hereby certify that the above is a true and complete log of Sunray Oil Corporation's #4 Almquist, located in NE Cor. NE/4 SW/4, Section 5 - 20S - 16W Pawnee County, Kansas.

Fred E. Stickle

Sworn to and subscribed before me this 23rd day of January, 1947

Viola Beck
Notary Public

RECEIVED
STATE CONSERVATION COMMISSION

DEC 2 1982

CONSERVATION DIVISION
Wichita, Kansas

3771
2020