

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Pawnee County, Sec. 11 Twp. 20S Rge. 16 ~~XXX~~ (W)
NE NE NE (330' PNL & 330' FEL)

NORTH

			#1

Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines
Lease Owner Magnolia Petroleum Company
Lease Name George KNOCHE Well No. 1
Office Address Box 770 - Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 12-27-45 19
Application for plugging filed 6-20-57 19
Application for plugging approved 6-21-57 19
Plugging commenced 6-31-57 19
Plugging completed 6-24-57 19
Reason for abandonment of well or producing formation Not economical to operate
If a producing well is abandoned, date of last production 3-17-57 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage
Producing formation Arbuckle Depth to top Bottom Total Depth of Well 3748 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle	Oil & Water	3695	3748	8-5/8"	1033	None
				5-1/2"	3737	2520

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged w/sand 3748' to 3720' - 5 sx cmnt. PB to 3680'. Shot 5-1/2" csg @ 2685', 2612' & 2532'. Pulled 40 jts 5-1/2" csg. Pulled 42 jts 5-1/2" csg. Total 82 jts - 2520'. Pulled off Bradenhead. Filled hole w/mud to 400' - 5' rock bridge 20 sx cmnt hole filled to 340'. Filled hole w/mud to 20'. 5' rock bridge - 5 sx cmnt to base of cellar. Filled to surf w/dirt.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ace Pipe Pulling Co.
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Pawnee, ss.
C. O. Turner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *C. O. Turner*
Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 25th day of June, 1957

My commission expires January 11, 1961
Notary Public.

PLUGGING
FILE SEC 11 T 20 R 16W
BOOK PAGE 22 LINE 10

JUN 26 1957
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

George Knoche #1
 NE NE NE
 Sec 11-20S-16W
 Pawnee County, Kansas

Elevation 2008'
 Total Depth 3748'

CASING POINTS:

8-5/8" lapweld set @ 1033 w/475 sx cmnt
 5-1/2" seamless set @ 3737 w/200 sx cmnt

RIG COMMENCED 12-2-45
 RIG COMPLETED 12-3-45
 DRILLING COMMENCED 12-3-45
 DRILLING COMPLETED 12-27-45
 PLUGGING COMMENCED 6-21-57
 PLUGGING COMPLETED 6-24-57

INITIAL PHYSICAL POTENTIAL: 214 BO + 143 BWPD

FORMATION SUMMARY:

Formation	Top	Bottom
Sand & red bed	0	160
Shale & shells	160	405
Shale	405	427
Sand & shale	427	580
Shale & shells	580	1029
Anhydrite	1029	1033
Shale & shells	1033	1950
Shale & lime	1950	2015
Lime	2015	2060
Shale & lime	2060	2148
Lime	2148	2370
Shale	2370	2400
Shale & lime	2400	2575
Lime	2575	2660
Shale & shells	2660	2800
Lime	2800	2890
Lime & Shale	2890	3010
Lime	3010	3670
Top Lansing	3398	
Lime & shale	3670	3730
Lime	3730	3737
Top Arbuckle	3695	

STANDARDIZED

Drilled Lime	3737	3739
Drilled	3739	3748

PLUGGING AND ABANDONMENT RECORD:

Plugged w/sand 3748' to 3720' - 5 sx cmnt. PB to 3680'. Shot 5-1/2" csg @ 2685', 2612' & 2532'. Pulled 40 jts 5-1/2" csg. Pulled 42 jts 5-1/2" csg. Total 82 jts - 2520'. Pulled off Bradenhead. Filled hole w/mud to 400' - 5' rock bridge 20 sx cmnt hole filled to 340'. Filled hole w/mud to 20'. 5' rock bridge - 5 sx cmnt to base of cellar. Filled to surf w/dirt.

SUPERVISED BY: Mr. R. M. Brundage, State District Plugging Supervisor.

PLUGGING	
FILE	SEC...11...T...20...R...16W
BOOK	PAGE...22...LINE...10

RECEIVED
 STATE CORRELATION DIVISION

CONSULTATION DIVISION
 Wichita, Kansas