


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Pawnee County, Sec. 11 Twp. 20S Rge. 16 (W)

Location as "NE/CNW/SW" or footage from lines C NE SW
Lease Owner John C. Graves, et al
Lease Name Franklin Well No. 1
Office Address 412 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 7, 19 65
Application for plugging filed July 7, 19 65
Application for plugging approved July 7, 19 65
Plugging commenced July 7, 19 65
Plugging completed July 7, 19 65
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3745 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Mudded up with heavy mud to 500 feet. Followed by wooden plug and 1/4 sack hulls. Placed 50 sacks cement onto hulls. Mudded up with heavy mud to 235 feet followed by wooden plug, 1/4 sack hulls and 40 sacks cement. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/4 sack hulls and 10 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 15 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Graves Drilling Co., Inc.
Address 412 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF BUTLER, ss.
John C. Graves (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves
412 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of July, 19 65

My commission expires April 30, 1967 Betty Brandt Notary Public.

ROTARY DRILLERS' LOG

OPERATOR: John C. Graves, et al DRILLING COMMENCED: June 30, 1965
 412 Union Center
 Wichita, Kansas.

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: July 7, 1965
 412 Union Center
 Wichita, Kansas

CASING RECORD: 8 Jts. 242' 8-5/8" LOCATION: Franklin No. 1
 cemented with 200 sacks. C NE SW
 Section 11-20S-16W
 Pawnee County, Kansas

0 - 241	Sand & shale
241 - 415	Shale
415 - 560	Sand
560 - 1034	Shale
1034 - 1057	Anhydrite
1057 - 1070	Shale
1070 - 2042	Shale & lime
2042 - 2378	Lime
2378 - 3433	Lime & shale
3433 - 3722	Lime
3722 - 3734	Lime & shale
3734 - 3745	Lime
3745	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 15 1965
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John C. Graves
President

STATE OF KANSAS)
) SS:
BUTLER COUNTY)

Subscribed and sworn to before me, a Notary Public, this 13th day of July, 1965.

Betty Brandt
Betty Brandt Notary Public

My commission expires:
April 30, 1967