


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Pawnee County, Sec. 19 Twp. 20 Rge. (E) 16 (W)

Location as "NE/CNW/SW" or footage from lines NW NW SE
Lease Owner IRON DRILLING COMPANY
Lease Name Wildgen Well No. 1
Office Address 1206 Philtower, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 6-26-56 19
Application for plugging filed 6-26-56 19
Application for plugging approved 6-26-56 19
Plugging commenced 6-26-56 19
Plugging completed 6-26-56 19
Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage
Producing formation None Depth to top Bottom Total Depth of Well 3903 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner		3424		730	8-5/8	None
Toronto		3442				
Douglas		3452				
Lensing		3503				
Marmaton		3740				
Conglomerate		3820				
Arbuckle		3865				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with heavy mud to 300 feet.
Cement plug set @ 300 feet using 20 sacks of cement and 1/3 sack of hulls.
Hole filled with mud to 35 feet. Cement plug set using 20 sacks of cement and 1/3 sack of hulls, filled hole to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUL 21 1956

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor IRON DRILLING COMPANY
Address 1206 Philtower, Tulsa, Oklahoma

STATE OF Oklahoma COUNTY OF Tulsa, ss.
J. L. Stackpole (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. L. Stackpole
1206 Philtower, Tulsa, Oklahoma
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of July, 19 56

My commission expires Feb. 28, 1960

B. Michal
Notary Public.

PLUGGING
FILE SEC 19 T. 20 R. 16 W
BOOK PAGE 74 LINE 44

DRILLING RECORD

Well: WILDGEN NO. 1
 NW NW SE, Sec. 19-20S-16W
 Pawnee County, Kansas

720' 8-5/8" Surface Casing
 cemented w/325 sacks.

Work Commenced: 6-12-56
 Drilling Commenced: 6-13-56
 Drilling Completed: 6-25-56
 Work Completed: 6-26-56

WELL LOG

Top soil & clay	0 to 40
Sand & gravel	40 to 125
Blue shale	125 to 190
Sand & shale	190 to 635
Sand, shale & shells	635 to 730
Red bed	730 to 1081
Anhydrite	1081 to 1120
Shale & shells	1120 to 1340
Shale & lime	1340 to 2265
Lime	2265 to 2330
Lime & shale	2330 to 2460
Lime	2460 to 2465
Shale & lime	2465 to 3391
Lime	3391 to 3436
Lime & shale	3436 to 3543
Lime	3543 to 3715
Lime & shale	3715 to 3813
Lime	3813 to 3837
Conglomerate	3837 to 3866
Arbuckle	3866 to 3883
	3903 T.D.

State of Oklahoma)
 County of Tulsa)

J. L. Stackpole, employee of owner of the above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

RECEIVED
 STATE CORPORATION COMMISSION

JUL 21 1956

J. L. Stackpole

Subscribed and sworn to before me this 5th day of July, 1956.

CONSERVATION DIVISION
 Wichita, Kansas

B. Michal

My commission expires:
 February 28, 1960

PLUGGING
 FILE SEC. 19 T. 20 R. 16W
 BOOK PAGE 74 LINE 44