


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Pawnee County, Sec. 34 Twp. 20S Rge. 16 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines. NE NW SE  
Lease Owner Tenneco Oil Company  
Lease Name Maurine Rutt Well No. 1-34  
Office Address 2000 Classen Center, Oklahoma City, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed May 7 19 71  
Application for plugging filed May 7 19 71  
Application for plugging approved May 7 19 71  
Plugging commenced May 7 19 71  
Plugging completed May 7 19 71  
Reason for abandonment of well or producing formation No Productible Zone



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3820 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1020	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Gunned up pits forming heavy mud. Filled hole with heavy mud and spotted 40 sacks cement at 400 feet. Filled hole with heavy mud, pushed 1/2 sack hulls and wooden plug to 40 feet, and capped with 10 sacks cement to base of well cellar. Job complete at 2:00 PM, May 7, 1971.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 17 1971

CONSERVATION DIVISION  
Wichita, Kansas

RECEIVED

MAY 13 1971

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Garvey Drilling Company  
Address Box 1164, Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.  
Ben E. Unruh (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ben E. Unruh  
Box 1164, Great Bend, Kansas 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of May 19 71

My commission expires July 8, 1974



James A. Thomas  
Notary Public.

# WELL LOG

COMPANY Tenneco Oil Company  
 FARM Maurine Rutt NO. 1-34  
 TOTAL DEPTH 3820'  
 COMM. 4-30-71  
 CONTRACTOR Garvey Drilling Company

SEC. 34 T. 20S R. 16W

LOC. NE NW SE

COUNTY Pawnee, Kansas

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAY 13 1971  
 CONSERVATION DIVISION  
 Wichita, Kansas


CASING  
 8 5/8" @ 1020' w/500sx

ELEVATION

PRODUCTION: D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

- 425' Surface Clay & Shale
- 555' Sand
- 690' Shale
- 1020' Anhydrite
- 1875' Shale w/Lime streaks
- 2125' Lime & Shale
- 2745' Shale & Lime
- 3220' Lime
- 3769' Arbuckle
- 3820' Arbuckle
- 3820' RTD

State of Kansas }  
 County of Barton } ss

I, Charlene Marker of Garvey Drilling Company  
 upon oath state the above and foregoing is a true and correct copy of the log of the Maurine Rutt 1-34 well.

Subscribed and sworn to before me this 11th day of May 19 71  
Charlene Marker

My Commission Expires: July 8, 1974  
Notary Public