


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

NORTH



Locate well correctly on above
Section Plat

Pawnee County, Sec. 4 Twp 20 Rge. 16 (E/W) (W)

Location as "NE/CNW/SW" or footage from lines SW NE NW

Lease Owner Kathol Petroleum, Inc.

Lease Name Hagerman 'A' Well No. 3 SWD

Office Address 900 Sutton Place, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) SWD

Date well completed July 29, 19 55

Application for plugging filed September 2, 19 70

Application for plugging approved September 3, 19 70

Plugging commenced September 4, 19 70

Plugging completed September 4, 19 70

Reason for abandonment of well or producing formation Lease Depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Depth to top Bottom Total Depth of Well 3806 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	804	None
				5-1/2"	3805	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pumped 2,500 lbs. gell, 200 lbs. cotton seed hulls, 3,100 lbs. port. cement and 2,367 lbs. pozzalin to T.D.

Pumped 50 sacks port. cement into surface casing

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

Address

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Domer J. Catt

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Domer J. Catt


900 Sutton Place, Wichita, Kansas

(Address)

Subscribed and sworn to before me this 27th day of October, 1970

My commission expires June 19, 1972

Katherine A. Stitt
Katherine A. Stitt Notary Public.



BEN F. BRACK OIL COMPANY, INC.
 309-10 BROWN BUILDING
 WICHITA 2, KANSAS

HAGERMAN "A" #3

SW NE NW

Sec. 4-203-16W
 Pawnee County, Kansas
 Commenced: 7-15-55
 Completed: 7-29-55

TOTAL DEPTH: 3806'
 ELEVATION: 2016' DF
 2014' Gr

WELL LOG

Surface Soil	0 -	15'
Shale		123
Shale & Iron Streaks		440
Sand		595
Shale		620
Sand		670
Red Bed		1060
Anhydrite		1090
Shale & Shells		1930
Shale & Lime		2055
Shale		2067
Lime & Shale		2210
Lime		2260
Shale & Lime		2310
Lime		2370
Lime & Shale		2500
Shale & Lime		2615
Lime & Shale		2660
Shale & Shells		2830
Lime & Shale		2945
Shale & Lime		3007
Lime		3251
Lime & Shale		3320
Lime		3357
Lime & Shale		3430
Lime		3806' T.D.

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 3 1970
 CONSERVATION DIVISION
 Wichita, Kansas

The above depths denote bottom of formations.

CASING

8 5/8" 804'
 5 1/2 3805'

To the best of my knowledge, the above is a true and correct statement of the depths and formations and where found.

BEN F. BRACK OIL COMPANY, INC.

By Bernard W. Grant

WITNESSED:

Gertrude Crist

August 12, 1955.

BEN F. BRACK OIL COMPANY, INC.
309-10 BROWN BUILDING
WICHITA 2, KANSAS

HAGERMAN "A" #3
TOTAL DEPTH: 3806'
ELEVATION: 2016' DF
2014' Gr

SW NE NW

Sec. 4-20S-16W
Pawnee County, Kansas
Commenced: 7-15-55
Completed: 7-29-55

WELL LOG

Surface Soil	0 -	15'
Shale		123
Shale & Iron Streaks		440
Sand		595
Shale		620
Sand		670
Red Bed		1060
Anhydrite		1090
Shale & Shells		1930
Shale & Lime		2055
Shale		2067
Lime & Shale		2210
Lime		2260
Shale & Lime		2310
Lime		2370
Lime & Shale		2500
Shale & Lime		2615
Lime & Shale		2660
Shale & Shells		2830
Lime & Shale		2945
Shale & Lime		3007
Lime		3251
Lime & Shale		3320
Lime		3357
Lime & Shale		3430
Lime		3806' T.D.

RECEIVED
STATE CORPORATION COMMISSION
FEB 3 1970
CONSERVATION DIVISION
Wichita, Kansas

The above depths denote bottom of formations.

CASING

8 5/8" 804'
5 1/2 3805'

To the best of my knowledge, the above is a true and correct statement of the depths and formations and where found.

BEN F. BRACK OIL COMPANY, INC.

By Bernard A. East

WITNESSED:

Arthur C. East

August 12, 1955.