

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD #1  
 K.A.R.-82-3-117

15.145.19081.0001

API NUMBER 5/19/77

LEASE NAME Hagerman

WELL NUMBER 1

2970 Ft. from (S) Section Line

2310 Ft. from (E) Section Line

SEC. 4 TWP. 20S RGE. 16 (E) or (W)

COUNTY Pawnee

Date Well Completed \_\_\_\_\_

Plugging Commenced \_\_\_\_\_

Plugging Completed 4-27-93

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR American Energies Corporation for Double B Oil Company

ADDRESS 2411 Dellrose Wichita, Kansas 67220

PHONE# (316) 685-2393 OPERATORS LICENSE NO. 6563

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/22/92 (date)

by Richard Lacy and Dwayne Rankin (KCC District Agent's Name).

Is ACO-1 filed? NO If not, is well log attached? NO

Producing Formation Abuckle Depth to Top 3700' Bottom 4132 T.D. 4132

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
ARBUCKLE	water	3700-4132		8 5/8	845'	None 450 Sacks
				5 1/2	3740'	None 100 Sacks
						75' Sacks 8 5/8-5 1/2

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 0 feet to 4132 feet each set. Allied Cementing pumped down 5 1/2 casing 600 lbs hulls 75 sacks 60-40 Poz 2%CC 20 sacks gel and 100 lbs hulls, 105 sacks 60-40 Poz 2%CC. Pressure to 500 lbs, standing pressure 50 lbs. Pumped 15 sacks 60-40 Poz 2% gel between 8 5/8" and 5 1/2" casing. Job complete 4:00 P.M. April 27, 1993. Fill 5 1/2" to surface ready mix, cut off 5 1/2".

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Chase Well Service, Inc. License No. 6123

Address P.O. Box 355 Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

Charles W. Steincamp (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well and I believe that the same are true and correct, so help me God.


(Signature) Charles W. Steincamp

(Address) P.O. Box 355 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 6th day of May, 19 93

Wendy L. Brackeen  
 Wendy L. Brackeen Notary Public

My Commission Expires: 2-23-97



RECEIVED  
 STATE CORPORATION COMMISSION  
 MAY 7 1993  
 CONSERVATION DIVISION  
 WICHITA, KANSAS