


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Pawnee County. Sec. 4 Twp. 20 Rge. 16 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines NE NE SW  
Lease Owner KATHOL PETROLEUM, INC.  
Lease Name HANKEN Well No. 1  
Office Address 900 Sutton Place, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed October 4 1950  
Application for plugging filed November 4 1968  
Application for plugging approved November 8 1968  
Plugging commenced November 15 1968  
Plugging completed November 19 1968  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production October 30 1968  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Arbuckle Depth to top 3707 Bottom 3710 Total Depth of Well 3710 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Kansas City	Lime	3475	3515	8-5/8	860'	None
Arbuckle	Lime	3707	3710	5-1/2	3708'	2640'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sand from 3719' to 3690'  
Dump 5 sacks cement, 40 bbls water.  
Plug 2640' - 2 sacks hulls, 20 sacks gel, 100 sacks cement.


RECEIVED  
STATE CORPORATION COMMISSION  
DEC 4 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Ralph Comstock Pipe Pulling  
Address 320 North Park, Stafford, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Homer Catt (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Homer Catt  
900 Sutton Place, Wichita, Kansas  
(Address)

Subscribed AND SWORN to before me this 3rd day of December, 1968  
My commission expires March 22, 1971  
Betty M. Maloney  
Betty M. Maloney Notary Public.



BEN F. BRACK OIL COMPANY, INC.  
309-10 BROWN BUILDING  
WICHITA, KANSAS.

HANKEN #1

NE NE SW Sec. 4, T. 26 S. R. 16 West  
Pawnee County, Kansas.

COMMENCED: July 8, 1950

COMPLETED: July 21, 1950

TOTAL DEPTH : 3710'

DRILLERS LOG

Cellar	5'
Clay, Shells and Shale	185
Chale and Shells	420
Shale and Shells	450
Sand	550
Sand and Red Bed	830
Red Bed	860
Red Bed	1050
Anhydrite	1090
Red Bed	1125
Red Bed and Shale & Shells	1360
Red Bed and Shale	1520
Salt and Shale	1765
Sahle and Lime streaks	1915
Lime and Shale	2035
Broken Lime	2120
Shale and Lime	2235
Lime and Shale	2300
Lime	2380
Lime and S hale	2485
Broken Lime	2590
Lime and Shale	2655
Shale and Lime	2695
Lime and Shale	2800
Lime and Shale	2885
Lime and Shale	2975
TOPEKA TOP	2865
Shale and Shells	3045
Lime and Shale	3100
Lime and Shale	3175
Lime	3235
Lime and Shale	3305
Lime	3345
Shale and Shells	3425
Lime - KANSAS CITY	3475
Lime	3515
Lime	3585
Lime	3630
Lime	3695
Lime and ARBUCKLE	3710
ARBUCKLE TOP	3707
TOTAL DEPTH	3710

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 8 1950  
CONSERVATION DIVISION  
Wichita, Kansas

To the best of my knowledge the  
above is a true copy of all  
formations and where found.

BEN F. BRACK OIL COMPANY, INC.

By

President

BFB:lb

WITNESSED:

*B. F. Brack*

DATED: September 29, 1950