

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Pawnee SEC. 4 TWP. 20s RGE. 16w E/W  
Location as in quarters or footage from lines:  
NE SW NW


Locate Well  
correctly on above  
Section Platt.

Lease Owner N-B Company, Inc.  
Lease Name Hagerman #1 Well No. \_\_\_\_\_  
Office Address P.O. Box 506, Russell, Kansas 67665  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 5/2/83  
Plugging completed 6/9/83  
Reason for abandonment of well or producing formation \_\_\_\_\_

Depleted  
Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3805'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	863'	none
				5 1/2"	3804'	2915'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged off bottom with sand to 3700' & ran 5 sacks cement, Shot well at 3318', 3006', & 2922'. Pulled total of 78 joints. Plugged well with 3 hulls, 10 gel, 50 cement, 10 gel, 1 hull, plug, & 150 sacks cement.

Plugging complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 347, Chase, Ks. 67524  
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of June, 1983

My Commission expires:



Irene Hoover  
Notary Public.

JUN 21 1983

CONSERVATION DIVISION  
Wichita, Kansas

15.145.21008.0000

EMPHASIS OIL OPERATIONS

P. O. Box 506  
Russell, Kansas 67665-0506

DRILLERS LOG

OPERATOR: N-B Company, Inc.  
P. O. Box 506  
Russell, Kansas 67665-0506

CONTRACTOR: Emphasis Oil Operations  
P. O. Box 506  
Russell, Kansas 67665-0506

LEASE: Hagerman WELL: #1

LOCATION: NE SW NW  
Section 4-20S-16W  
Pawnee County, Kansas

Total Depth: 3805'

Elevation: 2026' K.B.

Commenced: 3-10-83

Completed: 3-17-83

Casing: 8-5/8" @ 863' with 375 sks cement  
5-1/2" @ 3804' with 100 sks cement

Status: Oil Well

DEPTHS & FORMATIONS

(All measurements from K.B.)

Topsoil & Sand	42'	Shale	3453'
Shale	1072'	Lime & Shale	3751'
Anhydrite	1105'	Lime (L.T.D.)	3805'

RECEIVED  
STATE CORPORATION COMMISSION

APR 18 1983

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
                          ) ss:  
COUNTY OF RUSSELL)

Joe K. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

*Joe K. Branum*  
\_\_\_\_\_  
Joe K. Branum

Subscribed and sworn to before me this 23rd day of March, 1983.

My Commission Expires: February 6, 1984.



*Glenda R. Tiffin*  
\_\_\_\_\_  
Notary Public