

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Pawnee County, Sec. 22 Twp. 20 Rge. 16 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SE SE SW

Lease Owner Elreco and Huber

Lease Name Smith Well No. 1

Office Address Brown Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed Jan. 2 19 49

Application for plugging filed - 19

Application for plugging approved - 19


Plugging commenced 1-1-49 19

Plugging completed 1-1-49 19

Reason for abandonment of well or producing formation D&A

If a producing well is abandoned, date of last production D&A 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Name of Conservation Agent who supervised plugging of this well Agent at Great Bend

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations:

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface	clay sand	0	1057	8-5/8	1064	-0-
	Cemented with 500 sax					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud in hole to 250' of surface - mixed 15 sax cement ran cement plug at 250'
Mud to 30'
Mixed 10 sax cement ran plug to surface

RECEIVED
Conservation Div.
FEB 18 1949
STATE CORPORATION
COMMISSION
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to: El Dorado Refining Company
Address: Brown Building
Wichita 2, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, SS.
Chester Williams (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Chester Williams

604 Brown Bldg. Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 10th day of January 1949

Notary Public

My commission expires Nov. 3, 1952

PLUGGING
FILE SEC 22 T 20 R 16 W
BOOK PAGE 27 LINE 18

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
412 UNION NATIONAL BANK BUILDING - WICHITA, KANSAS

15.145.00410.0000

Over file

COMPANY **Elreco and Huber.**

SEC. 22 T. 20S R. 16W
LOC. SE SE SW

FARM **Smith**


NO. **1**

TOTAL DEPTH **3776**
COMM. **12-14-49**

COMP. **1-2-49**

COUNTY **Pawnee**

SHOT OR TREATED
CONTRACTOR **Flournoy and Williams**
ISSUED **1-8-49**



CASING
20 10
15 1/2 8 1/4
12 1/2 6 1/2
13 1/2 5 1/4

ELEVATION

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface clay 35
Sand 45
Shale and shells 404
Sand 555
Sand and shale 605
Red beds 950
Shale and shells 1052
ANHYDRITE 1079
Red Rock - shale 1380
Shale - shells 1565
Salt 1775
Lime 1795
Shale - shells 1830
Shale 1900
Lime 1970
Shale, Lime shells 2150
Lime 2235
Broken lime - shale 2525
Sandy lime - shale 2675
Shale - shells 2920
Shale - Lime 3045
Shale 3077
Shale - Lime 3230
Lime 3778

TOPS

Lansing 3460
Simpson 3753
Arbuckle 3768

DST 3770-76
Rec 570' Sulphur Water

COUNTY OF SEDGWICK

STATE OF KANSAS

SS:

Chester Williams, of lawful age, being first sworn says that the above is a true and correct copy of the log of the above well.

Chester Williams

Subscribed and sworn to before me this 10th day of January, 1949.

My commission expires Nov 3, 1952

Notary Public
Notary Public

PLUGGING
FILE SEC 22 T 20 R 16W
PAGE 77 LINE 18

RECORDED
AR 2 5 949
KANSAS