

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County, Sec. 22 Twp. 20 Rge. 16 (X) (W)

Location as "NE/CNW/SW" or footage from lines SE SE SE

Lease Owner Musgrove Petroleum Corporation & Rupp et al

Lease Name Bowman #1 Well No. 1

Office Address 518 Petroleum Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 11, 19 53

Application for plugging filed March 13, 19 53

Application for plugging approved 19

Plugging commenced March 11, 19 53

Plugging completed March 11, 19 53

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M.A. Rives

Producing formation Depth to top Bottom Total Depth of Well 3830 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1039'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Loaded hole with mud to 3000' set first plug at 900' with 20 sacks of cement.
Set second plug at 35' with 10 sacks of cement and 1/2 sack of hulls.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Musgrove Petroleum Corporation
Address 518 Petroleum Building, Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Gordon L. Koelling (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling
518 Petroleum Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 13th day of March, 19 53

My commission expires November 14, 1956.

Mary J. Dunbar Notary Public.

24-2675-S 2-52-20M

PLUGGING
FILE SEC 22 T 20 R 16 W
BOOK PAGE 84 LINE 5

RECEIVED
STATE CORPORATION COMMISSION
MARCH 14 1953
WICHITA, KANSAS

CONTRACTOR'S WELL LOG

COMPANY: Musgrove Petroleum Corporation & Rupp et al
 CONTRACTOR: Musgrove Petroleum Corporation
 FARM: Bowman # 1 -
 LOCATION: SE SE SE Section 22-20-16
 Pawnee County, Kansas

COMMENCED: February 23, 1953
 COMPLETED: March 11, 1953

0	40	Surface clay and sand
40	435	Clay and Sand
435	660	Shale and sand
660	1034	Red bed and shale
1034	1036	Chalky lime
1036	1065	Anhydrite
1065	2042	Lime and shale
2042	2115	Lime
2115	3775	Lime and shale
3775	3806	Conglomerate
3806	3830	Lime and shale
	3830	Rotary Total Depth

Set 1039' of 8 5/8" cemented with 450 sacks of cement.

Dry and abandoned.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the Bowman # 1, Section 22-20-16, Pawnee County, Kansas as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

By Gordon L. Koelling
 Secretary-Treasurer

Subscribed and sworn to before me a Notary Public in and for Sedgwick County, Kansas, this 13th day of March, 1953.

Mary L. Sumner
 Notary Public

My Commission Expires: November 14, 1956.

RECEIVED
 MUSGROVE PETROLEUM CORPORATION
 MARCH 14 1953
 CONSERVATION DEPARTMENT
 WICHITA, KANSAS

PLUGGING
 FILE SEC 22-20-16W
 BOOK PAGE 84 LINE 5