


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
221 No. Broadway
Wichita, Kansas

Ness County, Sec. 14 Twp. 20 Rge. (E) 24(W)

Location as "NE/CNW/SW/W" or footage from lines C SE SW NE
Lease Owner Cooperative Refinery Association
Lease Name Petersilie "A" Well No. 1
Office Address Box 765 Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 7-24 19 58
Application for plugging filed 8-7- 19 59
Application for plugging approved 8-11 19 59
Plugging commenced 8-11 19 59
Plugging completed 8-20 19 59
Reason for abandonment of well or producing formation
Non-commercial production
If a producing well is abandoned, date of last production 8-3 19 59
Was plugging obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker
Producing formation Mississippi Depth to top 4389 Bottom 4395 Total Depth of Well 4459 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	508'	-0-
				5 1/2"	4458'	2254.85'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded back from 4459' to 4430', dumped 4 sx. cement, Pulled pipe, mudded hole to 500', 10' rock bridge to 490', dumped 20 sx. cement, mudded to 40', 10' rock bridge, dumped 10 sx. cement. Complete

RECEIVED
STATE CORPORATION COMMISSION
AUG 26 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Wilson, Inc.
Address Stafford, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
John H. Nation (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John H. Nation
Box 765 Gt. Bend, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 24 day of August, 19 59

My commission expires Sept. 24, 1960

Yvonne Adams
Notary Public.

PLUGGING
FILE SEC 14 T. 20 R. 24 W
BOOK PAGE 88 LINE 31

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15.135.00668.0000

Company- COOPERATIVE REFINERY ASSOCIATION
Farm- Petersilie "A" No. 1

SEC. 14 T. 20 R. 24W
SE SW NE

Total Depth. 4459'
Comm. 7-8-58 Comp. 7-24-58
Shot or Treated.
Contractor. Shields Drilling Co.
Issued. 11-8-58

County Ness KANSAS



CASING:

8 5/8" @ 508' w/308 sx.
5 1/2" @ 4458' w/75 sx.

Elevation. 2302' RB

Production. 18 BOPD

Figures indicate Bottom of Formations.

shale	260
shale & lime	410
sand	445
shale & lime	508
shale, shells, sand, redbed	912
Anhydrite	927
redbed & sand	1290
shale	1535
lime	1560
shale & shells	1970
lime & shale	3902
lime	4225
lime & shale	4256
lime	4459 RTD
Total Depth	

TOPS: (SCOUT)

Heebner	3702
Toronto	3721
Lansing	3751
Base/Kansas City	4168
Marmaton	4192
Ft. Scott	4264
Cherokee	4288
Mississippi	4383