

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15.135.00148.0000

API NUMBER 12-20-57

LEASE NAME Petersilie A

WELL NUMBER 1

2310 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 14 TWP. 20 RGE. 24 (E) or (W)

COUNTY Ness

Date Well Completed 12-20-57

Plugging Commenced 12-17-96

Plugging Completed 12-18-96

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Joe Gerstner Oil

ADDRESS R.R. 1, Box 115 A, Ness City, Kansas 67560

PHONE (913) 798-2893 OPERATORS LICENSE NO. 9615

Character of Well oil

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on 12-18-96 (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? Yes if not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 4405

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface			8 5/8"	361	0
	Production			5 1/2"	4391	420

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Bottom plug sanded off to 4340'. 5 sks of cement. Tubing @ 800' Mixed 20 sks gel with 250 lbs. hulls circulated Mixed 310 sks 60/40 poz 6% gel 1/4" lb ELO seal per sk 150 lbs. hulls cement. Circulated 15 sks in cellar.

Name of Plugging Contractor D.S.& W. Well Servicing, Inc. License No. 6901

Address P.O. Box 231, Claflin, Kansas 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Joe Gerstner Oil

STATE OF Kansas COUNTY OF Barton, ss.

Joseph J. Strube (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Joseph J. Strube


(Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED AND SWORN TO before me this 30th day of December, 19 96

Karlynn K. Beck  
Notary Public

My Commission Expires: 09-28-98

USE ONLY ONE SIDE OF EACH FORM



Form CP-4  
Revised 05-88