

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

Ness County, Sec. 14 Twp. 20S Rge. 24 (E) (W)

Location as "NE/CNW/SW" or footage from lines NW SW SE

Lease Owner: Alco Oil and Gas Corporation
Lease Name: Petersilie
Office Address: 533 Petroleum Building, Wichita, Kansas Well No 3-A Twin

Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed May 26 19 59
Application for plugging filed May 23 19 60
Application for plugging approved May 23 19 60
Plugging commenced May 28 19 60
Plugging completed May 30 19 60

Reason for abandonment of well or producing formation non-commercial

If a producing well is abandoned, date of last production 4/20/60 19 60

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker

Producing formation Miss. Depth to top _____ Bottom _____ Total Depth of Well 4475 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	560	None
				5-1/2"	4475	3074

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back w/sand from 4444' to 4405'; mixed and dumped 5 sacks cement from 4405' to 4365'; pulled 3074' 5-1/2 casing. Mixed and dumped in 20 sacks G1 Mud, put in plug, mixed and pumped in 75 sacks cement from 225 ft. to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

AUG 18 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ace Pipe Pulling Company
Address P. O. Box 304, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Donald R. Douglass (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: "That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God."

(Signature) Donald R. Douglass
Donald R. Douglass
533 Petroleum Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16 day of August, 1960

My commission expires 2/23/64

Betty Baker
Betty Baker Notary Public.



DRILLERS LOG

Petersilie #3-A (Twin)

CASING RECORD: 8 5/8" @ 552'
w/300 sx Sunset

COMPANY: Artnell Company

CONTRACTOR: National Drilling Company, Inc.

COMMENCED: May 1, 1959

COMPLETED: May 17, 1959

DESCRIPTION: App. NW SW SE
14-20S-24W
Ness County,
Kansas

ELEVATION: 2311 KB
2309 DF

TOTAL DEPTH: 4475' (-2164)

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Clay	0	20	
Sand & Shale	20	285	
Shale, Shells & Redbed	285	560	
Shale	560	570	
Redbed	570	860	
Shale & Redbed	860	1350	
Shale & Shells	1350	1455	
Shale	1455	1760	
Shale & Shells	1760	2220	
Shale & Lime	2220	2265	
Lime	2265	2575	
Lime & Shale	2575	3570	
Lime	3570	3632	
Shale & Lime	3632	3945	
Lime	3945	4390	
Core	4390	4428	
Lime	4428	4475	

RECEIVED
STATE CORPORATION COMMISSION
SEP 4 1962
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

NATIONAL DRILLING COMPANY, INC.

Howard A. Stoskopf
Howard A. Stoskopf

Subscribed and sworn to before me this 16th day of July, 1959.

Ruby Gourley
Notary Public

RUBY GOURLEY
My commission expires July 13, 1960