

R
1

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 48-15

LOCATION SE-SE-SW.

SEC. 28 TWP. 16 RGE. 25W.

Dry Hole ✓ Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Hanlin Investments

Operator Herman Geo. Kaises Address 909 Palace Bldg. Tulsa OK 1A.

Field _____ County Ness

Total Depth 4.489 Feet.

Plugging Contractor R E E Pipe Pulling Co.

Plugging Contractor's License No. 2

Address 2905-16th Great Bend Kansas

(Describe Briefly the manner in which the well was plugged)

Surf Pipe 8 3/4 @ 225 feet c.w. - 5 1/2 Pipe @ 4.486 w/ 150 M.
top Perf. @ 4.455 - sand to 4.445 + 5 in. of cement. Pull 5 1/2
to 1100 feet and c.w. + oil out with yell mud + Pull 5 1/2 to
to 750 feet + Pump in 100 cu. y cement + Pull 5 1/2 to 450 feet and
Pump in 75 cu. y cement + Pull pipe out and bat set over
night and check cement at 20 feet + RR. and 5 cu.
y cement to base of cellar at 11 AM - Stake truck

R.M. Burdette
District Conservation Agent

Date 9-28-57

RECEIVED
STATE CORPORATION COMMISSION

10-1-57 OCT 1 - 1957
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 28 T 16 R 25W
BOOK PAGE 48 LI E 15