

15.159.21928.0000

2-090453

1-16

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER: 15-159-21,920

SE, SECTION 12 TOWNSHIP 20 RANGE 6  
SW

OPERATOR LICENSE # 32017 660 FEET FROM S SECTION LINE

OPERATOR ABC OIL & SALVAGE 330 FEET FROM E SECTION LINE

NAME & R.R. #3, BOX 151

ADDRESS LYONS, KS 67554

LEASE NAME: SNYDER #1

COUNTY: RICE

WELL TOTAL DEPTH: 3400' 110.50

PIPE: 5 1/2" @ 3340'

SURFACE CASING: 8 5/8" @ 209'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD  D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: QUALITY WELL SERVICE

ADDRESS: STERLING, KS LICENSE: 31925

COMPANY TO PLUG AT: HOUR: 13:00 DAY: 15 MONTH: 1 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: DISTRICT #2

COMPANY NAME: QUALITY WELL SERVICE PHONE: (316) 727-3410

WERE: SAND TO 3250' AND CAP WITH 5 SACKS OF CEMENT.

SHOOT PIPE FOR RECOVERY.

35 SACKS AT 970' AND 35 AT 890', CIRCULATE FROM 260' TO SURFACE.

PLUGGING PROPOSAL RECEIVED BY: DISTRICT #2

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL {  } PART {  } NONE {  }

COMPLETED: HOUR: 14:00 DAY: 16 MONTH: 1 YEAR: 1997

ACTUAL PLUGGING REPORT: SANDED TO 3250' AND CAPPED WITH 5 SACKS OF CEMENT.  
RECOVERED 2276 OF 5 1/2". THRU CASING, SPOTTED 35 SACKS AT 970' AND 35 SACKS AT  
870', CIRCULATED FROM 260' TO SURFACE.

REMARKS: 60/40 POZ 2% GEL 170 SACKS CEMENT, 400# HULLS  
UNITED #4879

**INVOICED**

DATE 2-3-97

INV. NO. 47496

**MAR 27 1997**

**RECEIVED**  
KANSAS CORPORATION COMMISSION

JAN 31 1997

CONSERVATION DIVISION  
WICHITA, KS

I DID OBSERVE THIS PLUGGING.

*Ralph Tittel*  
RALPH TITTEL

FORM CP-2/3  
REV. 3/90