


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling 1 Building
Wichita, Kan.

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 6 Twp. 20 Rge. 15 W. (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C. N/2 NW NE
Lease Owner Solar Oil Company
Lease Name Herman Behrens Well No. 2
Office Address 1117 Union Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed June 18, 19 45
Application for plugging filed May 23, 19 56
Application for plugging approved May 23, 19 56
Plugging commenced May 24, 19 56
Plugging completed May 30, 19 56
Reason for abandonment of well or producing formation Oil depleted

If a producing well is abandoned, date of last production July 1, 19 52
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage
Producing formation Arbuckle Depth to top 3643 Bottom 3755 Total Depth of Well 3755 Feet
Show depth and thickness of all water, oil and gas formations. 3733 Cement

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	995'8"	None
				5 1/2"	3756'	2706'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the-hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug back with sand to 3700'. Dump 5 sacks sand.
Pull 5 1/2" casing.
Mud hole to 300'. Set 5' rock bridge. Mix and
dump 20 sacks cement. Fill hole with mud to 35'.
Set 5' rock bridge. Mix and put in 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ace Pipe Pulling Company
Address Box 304, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
James Davis, Jr. (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James Davis, Jr.
1117 Union Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of June, 1956.

Leota Lee Miller
Notary Public.

My commission expires July 27, 1959

PLUGGING
FILE SEC. 6 T. 20 R. 15W
BOOK PAGE 64 LINE 4

JUN 11 1956
CONSERVATION DIVISION
Wichita, Kansas

6-11-1956


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - SOLAR OIL CORP.
Farm - Behrens No. 2

SEC. 6 T. 20 R. 15 W
CN/2 NW NE
575' FWL & 330' FNL NE 1/4

Total Depth. 3755'
Comm. 6-2-45 Comp. 6-18-45
Shot or Treated. Acidized w/2000 gals.
Contractor. Mouser Drlg. Co.
issued. 3-2-46

County. Barton
KANSAS



Elevation. 1984

Production. Phy. Pot. 26 B.

CASING:
8 5/8" 995' 8" Cem.
5 1/2" 3756' Cem.

Figures Indicate Bottom of Formations.

shale & sand	200	Perf. 3701-09' - 25 bullets
shale & shells	368	" 3705-18' - 46 "
Dakota sand	508	" 3718-22 1/2' - 30 "
red bed	560	
sand	572	Acidized w/1000 gals. XF20
red rock	630	" w/1000 gals. XF20 (Pilot)
red bed & shale	770	
red rock	990	
anhydrite lime	1000	
cement @ 1000		
anhydrite	1020	
shale & red bed	1060	
shale & shells	1280	
shale	1470	
salt & shale	1485	
shale & shells	1510	
shale & salt	1675	
shale & shells	1700	
lime & shale	1865	
lime	1925	
lime & shale	1940	
lime	2045	
lime & shale	2065	
lime sdy	2070	
lime & shale	2090	
lime	2130	
shale	2150	
lime	2245	
shale	2275	
lime	2310	
lime & shale	2675	
shale	2758	
lime	2825	
lime & shale	2883	
shale	2900	
lime & shale	3130	
lime	3316	
shale & lime	3334	
lime	3439	
lime hrd	3450	
lime	3460	
chalky lime	3475	
lime brkn	3480	
lime	3567	
lime brkn	3635	
lime	3755	
Total Depth		

STATE OF KANSAS)
COUNTY OF SEDGWICK)SS

I, James Davis, Jr., of the Solar Oil Company upon oath state that the above and foregoing is a true and correct copy of the log of the Behrens #2 well.

James Davis, Jr.
James Davis, Jr.

Subscribed and sworn to before me this
23rd day of May, 1956.

Leota Lee Miller
Leota Lee Miller
Notary Public

My commission expires:
July 27, 1959

Top of Cement 3733'

Tops:
Topoka 3130
Heebner 3295
Kans. City 3370
Arbuckle 3644

RECEIVED
STATE CORPORATION COMMISSION

JUN 11 1956

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 6 T. 20 R. 15W
BOOK PAGE 64 LINE 4