


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Barton County. Sec. 6 Twp. 20 Rge. 15 NW (W)
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines C. N/2. SW. NE
Lease Owner Solar Oil Company
Lease Name Herman Behrens Well No. 1
Office Address 1117 Union National Building Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed January 20, 1945
Application for plugging filed October 1, 1956
Application for plugging approved October 1, 1956
Plugging commenced October 1, 1956
Plugging completed October 19, 1956
Reason for abandonment of well or producing formation Oil depleted
If a producing well is abandoned, date of last production Sept. 25, 1956
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Brundage
Producing formation Arbuckle Depth to top 3659 Bottom 3755 Total Depth of Well 3755 Feet
Show depth and thickness of all water, oil and gas formations. Cement 3728

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	1005'	None
				5 1/2"	3755	3111'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug back with sand from 3728' to 3708' and dump 5 sacks cement with dump bailer. Pull casing. Mud hole to 335', set rock bridge from 335' to 325', mix and dump 20 sacks cement. Mud hole to 35', set rock bridge from 35' to 25' mix and pour 10 sacks cement from 25' to base of cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ace Pipe Pulling Company
Address Box 304, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

James Davis, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James Davis, Jr.
1117 Union National Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of October, 1956

Leota Lee Miller Notary Public.

My commission expires July 27, 1959

23-8390-s 6-51-20M

PLUGGING CONSERVATION DIVISION
SEC 6 T 20 R 15 W
BOOK PAGE 104 LINE 13
10-31-1956

WELL LOG

Company: Solar Oil Corporation
 County: Barton
 Lease: Behrens #1 C N/2 SW NE 6-20-15
 Driller: Campbell Drilling Company
 Well Commenced: November 22, 1944
 Well Finished: December 15, 1944
 POTENTIAL: 250 bbls. Phy.

ELEVATION - 1989

Barton County 760' from W.L. 990' from S.L.

8 5/8" - 1005' cemented w/400 sacks
 5 1/2" - 3755' cemented w/100 sacks

From	To	Description	Notes
0	40	Cellar	
40	275	Shale-Lime & Shells	
275	555	Shale	
555	750	Shale & Sand	
750	995	Red Bed	
995	1000	Red Bed & Shale	
1000	1021	Anhydrite	8 5/8" - 1005' cemented w/400 sacks
1021	1615	Shale & Shells	
1615	1750	Shale	
1750	2070	Shale & Lime	
2070	2145	Sandy Lime & Shale	
2145	2245	Lime	
2245	2320	Lime & Shale	
2320	2680	Shale & Lime	
2680	2770	Shale & Shells	
2770	2810	Lime	
2810	2902	Shale & Lime	
2902	2955	Lime	
2955	3150	Shale & Lime	
3150	3179	Broken Lime	
3179	3240	Lime & Shale	
3240	3298	Lime-Bro.	
3298	3400	Shale & Lime	
3400	3467	Lime	
3467	3481	Porous Lime & Sand	
3481	3607	Lime	Gas 3675-81, 3700-08'
3607	3695	Shale & Lime	Pay 3719-23
3695	3755	Sand-T.D.	5 1/2" - 3755' cemented w/100 sacks
	3728	Top of Cement	

Perforated from 3719-23' with 27 shots
 Acidized with 500 gallons

Top of Topeka - 3135' McKee
 Heebner - ~~3311~~ 3300
 K.C. - ~~3389~~ 3376
 Arbuckle - 3659'

APPROVED
 STATE GEOLOGICAL SURVEY

PLUGGING
 SEC. 6 T. 20 R. 15W
 BOOK PAGE 104 LINE 13

CONSERVATION DIVISION
 Wichita, Kansas