


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Blitting Building
Wichita, Kansas

NORTH



Locate well correctly on above Section Flat

Barton County. Sec. 6 Twp. 20-S Rge. (E) 15 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NE SE
Lease Owner The Bay Petroleum Corporation
Lease Name Amerada-Smith Well No. 2
Office Address Box 957, Denver Colorado
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed Jan 24 1947
Application for plugging filed May 22 1951
Application for plugging approved May 23 1951
Plugging commenced July 18 1951
Plugging completed July 27 1951
Reason for abandonment of well or producing formation Failure to produce in commercial quantity
If a producing well is abandoned, date of last production May 1951
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Stough
Producing formation Arbuckle Depth to top 3761 Bottom Total Depth of Well 3780 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	1010'	None
				5 1/2	3802'	3015'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded and rocked hole from 3780' to 3660' and ran 5 sacks cement. Mudded hole from 3610' to 250', set 10' rock bridge and ran 15 sacks of cement. Mudded hole to 35', set rock bridge and ran 10 sacks of cement. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Bay Petroleum Corporation
Address Box 513, Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, SS.
Forrest Crawford (employee of owner) or owner or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Forrest Crawford
(Address) _____

SUBSCRIBED AND SWORN to before me this 8 day of August, 1951

My commission expires May 20, 1954

23-5091-s

8-50-10

STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 6T 20 R 15W
BOOK PAGE 82 LINE 39

AUG 9 X 1951
CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
Notary Public.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - BAY PETROLEUM CORPORATION
Farm - Amerada-Smith No. 2

SEC. 6 T. 20. R. 15W
NW NE SE

Total Depth. 3776'
Comm. 8-26-47 Comp. 10-18-47
Shot or Treated.
Contractor. Glenn Peel Drlg. Co.
Issued. 11-8-47

County. Barton

KANSAS



Elevation. _____

Production. Pot. 1,342,000 Gas

Figures indicate Bottom of Formations.

surface clay	45
rock shale	250
shale & sand	355
shale	400
sand	510
shale & sand	670
shale & shells	940
red shale	998
anhydrite	1008
anhydrite	1025
shale & shells	1180
shale & shells	1520
salt	1690
shale & lime	2259
lime	2410
lime & shale	3150
lime	3205
lime & shale	3285
lime	3638
shale	3646
lime	3734
Dolomite	3739
Dolomite	3755
lime	3776

Total Depth 3776

TCPS:

Arbuckle 366L

Testing Information

DST 3734 $\frac{1}{2}$ -37 op 45", Rec. 20' OCM & 140'
Arb. salt water
Perf 12 shot with 3727-29-750' wtr first hr.
Perf 6 shot with 3722-24-50, 3 to 4 G W/30"
Perf. 3724-36 Bail 20 gals WPH W/ some oil
500 A - 1,125,000 gas, 2 BPPH/50% wtr.
Squeez-d 60 sx. cem., 3200# standing pressure
Perf 47 shot with 3670-78 - nice show gas
Some oil & 10 G WPH
500 A - Perf 36 shot with 3690-96
500A - GS gas-2000 A.
1,342,000 CFG, some oil.

PLUGGING
FILE SEC 6 T 20 R 15W
BOOK PAGE 83 LINE 39

RECEIVED
STATE CORPORATION COMMISSION
AUG 9 X 1951
CONSERVATION DIVISION
Wichita, Kansas

U.S. DEPARTMENT OF JUSTICE
FEDERAL BUREAU OF INVESTIGATION
WASHINGTON, D. C. 20535
APR 2 1964