

WELL PLUGGING RECORD

FORMATION PLUGGING RECORD

STATE OF KANSAS STATE CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 800 Bitting Building Wichita, Kansas

Strike out upper line when reporting plugging of formations.

BARTON County. Sec 7 Twp 20 Rge 15 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines NW SW NW

Lease Owner BEN F. BRACK OIL COMPANY, INC.

Lease Name DIRKS Well No. 1

Office Address # 309-10 BROWN BUILDING, WICHITA, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) OIL

Date well completed April 21, 1948 19

Application for plugging filed April 15, 1950 19

Application for plugging approved April 19, 1950 19


Plugging commenced April 19, 1950 19

Plugging completed April 19, 1950 19

Reason for abandonment of well or producing formation dry and not producing

If a producing well is abandoned, date of last production May 14, 1949 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Arbuckle Depth to top Bottom Total Depth of Well 3745 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Rows include Shale, clay and Sand Arbuckle with depth ranges and casing sizes.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 250 feet to 30 feet for each plug set.

Plugged back with Chat 3745' to 3725'. Dumped five (5) sacks of cement. Mudded hole up to 250', set 10' rock bridge and dumped fifteen (15) sacks of cement. Mudded hole to 30' and then dumped ten (10) sacks of cement.

STATE CORPORATION COMMISSION KANSAS JUN 2 1950 6-2-1950

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to BEN F. BRACK OIL COMPANY, INC. Address 309-10 BROWN BUILDING, WICHITA, KANSAS. L

STATE OF KANSAS COUNTY OF SEDGWICK ss. HENRY B. BRACK (Employer/owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) Henry B. Brack

309-10 BROWN BUILDING, WICHITA 2, KANS (Address)

SUBSCRIBED AND SWORN to before me this 11th day of MAY, 1950

Beulah Merrill Notary Public.

My commission expires Nov. 26, 1952

PLUGGING FILE SEC 7 TWP 20 RGE 15 BOOK PAGE 4 LINE 26

Dirks No. 1 Sec. 7-20-15W, Barton County, Kansas

WELL LOG

TOTAL DEPTH	3745'
Comm: 3-31-48	Comp: 4-16-48
Cellar	5'
clay, sand & Red Bed	240
Red Bed	275
Shale & shells	350
Blue clay	380
shale & shells	410
shells & sand	425
sand	560
shale & Red Bed	710
Red Bed	765
Red Bed & shale	1005
shale & Red Bed	1031
Anhydrite	1033
cement	1033
Anhydrite	1060
shale & Red Bed	1290
shale & salt	1545
Red Bed, shale & shells	1790
lime & shale	1890
lime	1995
lime	2095
lime	2165
lime	2225
lime	2300
lime	2350
lime & shale	2460
shale & lime	2575
shale & lime	2670
shale & lime	2775
shale & shells	2810
shale & lime	2920
lime & shale	2990
lime & shale	3070
lime & shale	3175
lime & shale	3250
lime & shale	3290
lime & shale	3350
Broken Lime	3390
lime & shale	3420
lime & shale	3455
lime	3525
lime	3576
shale & lime	3608
shale & lime	3650
lime & shale	3678
lime (Arbuckle)	3696
lime & shale	3730
lime & shale	3745

Dated: 4-21-48

Witness: Burton Merrill

PLUGGING
WELL NO. 7-T-30P15W
LOG PAUL L. LINE 24

RECEIVED
Commission Div.
JUN 2 X 1950
STATE CORPORATION
COMMISSION
KANSAS

To the best of my knowledge the above is a true and correct record of the formations and depths at which found.

BEN F. BRACK OIL COMPANY, INC.

By: Kenny Brack