

## WELL PLUGGING RECORD

..County. Sec. 7 Twp. 20S Rge. 15 (E) 15 (W)

Lease Owner Amerada Petroleum Corp.

Lease Name S. Deckert "B" Well No. #2

Office Address Box 2040, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 23, 19 49

Application for plugging filed.....19.....

Application for plugging approved.....19.....

Plugging commenced ..... June 23, 19 49

Plugging completed..... June 24, 19 49

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production..... 19.....

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well. Mr. C. D. Stough, Great Bend, Kansas

Producing formation..... Depth to top..... Bottom..... Total Depth of Well.....**3902'**..... Feet

Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

### CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to .....feet for each plug set.

Circulated heavy mud in hole. Set Halliburton plug at 200' down from top. Mixed & poured in 15 sacks cement through 4½" drill pipe. Filled hole up to within 30' of top with heavy mud. Set Halliburton plug, dumped in 10 sacks of regular cement filling hole to top of surface casing in cellar, as requested by State Plugger C.D. Stough of Great Bend, Kansas. Well Plugged and abandoned.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to..... **Amerada Petroleum Corp.**

Address..... Box 2040  
Tulsa, Oklahoma

STATE OF Oklahoma, COUNTY OF Tulsa, ss.

..... C. H. Rose (employee of owner) or ~~(owner or operator)~~ of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-  
described well as filed and that the same are true and correct. So help me, God. 1

(Signature)

SUBSCRIBED AND SWORN to before me this 6 day of July, 1949

My commission expires

22-5133-8

9-48-10M

.....  
*Notary Public.*

# PLUGGING

7-20-52  
107 41

Well No. 2  
 Farm Susie Deckert "B"  
 Elevation 2025' - Derrick Floor  
 Location NE/4 SE/4 NE/4  
 990' from South line  
 330' from East line  
 Section 7-20S-15W  
 Barton County, Kansas  
 Company Amerada Petroleum Corporation  
 Commenced Drlg. June 7, 1949  
 Completed Drlg. June 23, 1949  
 Contractor: Powell & Brunson  
 Initial Production: None - Dry Hole  
 No time log or electric log made.

CASING RECORD:	SIZE	WEIGHT	FEET	CEMENT	PERFORATIONS
	8-5/8"	28#	1036	500 Sx	None

FORMATION:

Shale and Shells	0	415
Sand	415	550
Red Bed	550	645
Shale & Shells	645	1027
Anhydrite	1027	1057
Red Bed	1057	1320
Shale & Shells & Salt	1320	1825
Lime	1825	2183
Chert	2183	2193
Lime	2193	2470
Shale & Lime	2470	2550
Shale & Shells	2550	2985
Broken Lime	2985	3155
Lime	3155	3660
Lime shale	3660	3705
Lime	3705	3902
TOTAL DEPTH		3902'

GEOLOGICAL TOPS

Anhydrite	1027'
Lansing	3428'
Arbuckle	3703'
Rotary tools used from	0'
	3902'

RECEIVED  
 COM. DIV. 100-100  
 JUL 16 1949  
 STATE CORPORATION  
 COMMISSION  
 KANSAS

**PLUGGING**  
 FILE SEC 7 T20 R 15u  
 BOOK PAGE 102 LINE 41