


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 7 Twp. 20 Rge. 15 (E) (W) W
Location as "NE/CNW/SW" or footage from lines SE SE NW
Lease Owner Ben F. Brack Oil Co., Inc.
Lease Name Dirks Well No. 2
Office Address 310 Brown Bldg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed May 13, 1948 19
Application for plugging filed Feb 9, 1957
Application for plugging approved Feb 9, 1957
Plugging commenced Feb 11, 1957
Plugging completed Feb 15, 1957
Reason for abandonment of well or producing formation gas depleted
If a producing well is abandoned, date of last production Dec 1956
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage
Producing formation Arbuckle Depth to top 3672 Bottom 3726 Total Depth of Well 3726 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surfacesoil, clay, gravel shale, shells, red bed and anhydrite		0	1019	8 5/8	1020	None
Lansing		3404				
Arbuckle		3672		4 "	3720	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back with sand to 3690'. Cleaned out cellar. Fill hole with water, dumped 4 sacks of cement with dump bailer. Mudded hole to 375', set 10 ft rock bridge, dumped 20 sacks of cement, mudded hole to 35' set rock bridge, ran 10 sacks of cement to top of surface pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor E & L Casing Pulling Co.
Address 1003 Heizer St. Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Bernard D. Grant (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bernard D. Grant
310 Brown Bldg, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 27th day of February, 1957

My commission expires Dec 27, 1960

RECEIVED
STATE CORPORATION COMMISSION
Notary Public.

24-7368-S 3-53-20M

PLUGGING
FILE SEC 7 T 20 R 15W
BOOK PAGE 139 L 25

D R I L L E R ' S : L O G

Operator:

Ben F. Brack Oil Co. Inc.
Wichita, Kansas

DIRKS #2
SE SW NW 7-20-15
Barton County, Kansas

Contractor:
Company tools

Started: 6-18-48
Completed: 7-10-48

ॐ नमो भगवते वासुदेवाय ॥

Surface Soil, sand shale	0	-	110
Blue shale			365
Red Beds			925
Anhydrite			1021
Salt			1405
Salt, shale & red bed			1600
Lime			2205
Lime & Shale			2415
Shale & lime			2980
Lime Broken			3155
Lime, Lansing & K.C.			3500
Lime-Cong.			3655
Lime			3726

CASING RECORD:

8 5/8" set at 1019'
4 1/2 set at 3726'

Depths denote bottoms of formations.

To the best of my knowledge, the above is a true and correct statement of the formations and where found.

BEN F. BRACK OIL COMPANY, INC.

By

Vice-President

Dated: March 25, 1957

Witnessed:

CONFIDENTIAL

WVL 52-114

2017 RELEASE UNDER E.O. 14176

SECRET

PLUGGING

FILE SEC 7 T 20 R 15W
BOOK PAGE 139 LINE 25