


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Pawnee County, Sec. 6 Twp. 20 Rge. 19 (X) (W)
Location as "NE/CNW/SW" or footage from lines NE NE NW
Lease Owner Frontier Oil Company
Lease Name Schneider Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 6 19 56
Application for plugging filed March 6 19 56
Application for plugging approved March 6 19 56
Plugging commenced 10:00 P.M. March 6 19 56
Plugging completed 11:00 P.M. March 6 19 56
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes, by telephone

Name of Conservation Agent who supervised plugging of this well Mr. Bundridge
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	207'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 240 ft. Ran 1/3 sack hulls, plug, and 25 sacks cement through drill pipe. Filled hole with mud to 35 ft. Ran 1/3 sack hulls, plug, and 10 sacks cement.

3-10-1956

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Kiefer & Krause Drilling Co., Inc.
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, SS.
Richard B. Krause (contractor for owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Richard B. Krause
for Kiefer & Krause Drilling Co., Inc.
Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 8th day of March, 19 56

My commission expires July 29, 1957

24-7368-5 3-53-20M

PLUGGING
FILE SEC 6 T 20 R 19 W
BOOK PAGE 44 LINE 11

Notary Public.

DRILLERS LOG

COMPANY: Frontier Oil Company

SEC: 6 T20S R19W
Pawnee County, Kansas

FARM: Schneider No. 1

LOC: NE/4 NE/4 NW/4

TOTAL DEPTH: 4680'

COMM: 2-13-56 COMP: 3-6-56

CONTRACTOR: Kiefer & Krause Drilling Co., Inc.

CASING: 8 5/8" 207'

ELEVATION: 2251' D.F.

0	15	Surface Soil
15	207	Blue Shale
207	285	Shale & Sand
285	412	Shale & Shells
412	751	Blue Shale
751	906	Red Shale
906	1061	Sand
1061	1155	Shale
1155	1300	Shale Red Beds
1300	1335	Lime
1335	1415	Shale & Lime
1415	1730	Shale & Shells
1730	1890	Shale
1890	2080	Lime & Shale Stks.
2080	2203	Lime & Shale
2203	2234	Lime
2234	2390	Lime & Shale
2390	2415	Shale
2415	2600	Shale & Lime
2600	2630	Lime & Shale
2630	2915	Lime
2915	3265	Lime & Shale
3265	3379	Shale & Lime
3379	3465	Lime & Shale
3465	3593	Lime
3593	3635	Shale
3635	3738	Shale & Lime
3738	3745	Lime
3745	3820	Lime & Shale
3820	4680	Lime

Cemented 8 5/8" casing at 207 ft. with 200 sacks cement.

4680 Total Rotary Depth Plug 1 to 240 ft.; ran 1/3 sack hulls and 25 sacks cement. Plug 2 to 35 ft.; ran 1/3 sack hulls and 10 sacks cement.

I certify that this is the true and correct copy of the above log to the best of my knowledge.

[Signature]
for Kiefer & Krause Drilling Co., Inc.

Subscribed and sworn to before me this 8th day of March, 1956.

[Signature]
Notary Public

My Commission Expires July 29, 1957

PLUGGING
 FILE SEC 6 T 20 R 19W
 BOOK PAGE 44 LINE 11