

6 062068

1-29

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 009-23,673 . 0000

SE , SEC. 22 , T 20S, R 15 W/E

660 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6149

Lease Name Miller Well # 1

Operator: Dunne Equities Inc.

County Barton 118.85

Name & Address 8100 E 22nd Street North  
Wichita, Ks. 67226

Well Total Depth 3657 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 709

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering Inc. License Number 5111

Address Box 698 Great Bend, Ks. 67530

Company to plug at: Hour: 10:00 AM Day: 29 Month: Jan Year: 19 90

Plugging proposal received from Jim Rockhold

(company name) Rockhold Engineering Inc. (phone)

were: Order 200 sks 60/40 poz 8% gel 5 sks hulls.

Ran line to 1000'

Plugging Proposal Received by Gilbert G. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 1:15PM Day: 29 Month: Jan Year: 19 90

ACTUAL PLUGGING REPORT 8 5/8" set at 709' w/315 sks. 5 1/2" set at 3755' w/150 sks. Top perf at 3673'. Plugged bottom w/sand and 5 sks cement to 3625'. Shot pipe four times and recovered 1947'. Pumped in 8 5/8" 25 sks cement followed w/5 sks hulls in 175 sks cement w/500 psi.

RECEIVED STATE CORPORATION COMMISSION

Remarks: By Allied. FEB 14 1990 (If additional description is necessary, use BACK of this form.)

INVOICED

CONSERVATION DIVISION Kansas

Signed Gilbert G. Scheck (TECHNICIAN)

DATE 2-15-90

INV. NO. 27454