

9-8

4-010290

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-009-01,022-0001

E2 E2 SE /4 SEC. 22, 20 S, 15 W
1320 feet from S section line
330 feet from E section line

Operator license# 30737

Lease: Miller OWWO Well # 2

Operator: M.A. Yost

County: Barton 119.05

Address: Box 811
Russell, Kansas 67665

Well total depth 3663 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 10 3/4 Inch @ 798 feet

Aband. oil well Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Allied Cementing License# -

Address: _____

Company to plug at: Hour: 3:00P.M. Day: 8 Month: September Year: 1997

Plugging proposal received from: Richard McIntyre

Company: Quality Well Service Phone: _____

Were: Same as below. 9-15-1999

RECEIVED
SEP 15 1999
15:52

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All , Part [], None []

Completed: Hour: 6:00 P.M., Day: 8, Month: September, Year: 1997

Actual plugging report: Sanded to 3523' and dumped 5 sxs. Shot off pipe at 1828'. Pulled to 1750' and pumped 125 sxs 60/40 pozmix - 10% gel - 2% C.C. with 300# hulls. Pulled to 950' and pumped 40 sxs with 100# hulls. Pulled to 475' and pumped 85 sxs. Pulled to 150' and pumped 40 sxs with 200# hulls. Part swedge and pumped 15 sxs. Max. P.S.I. 600#. S.I.P. 400#.

Remarks: Well flowing on backside.

Condition of casing(in hole): GOOD BAD _____ Anhy.plug: YES NO _____
Bottom plug(in place): YES _____, CALC _____, NO _____ Dakota plug: YES , NO _____
Plugged through TUBING _____, CASING . Elevation: _____ GL

I did / did not [] observe the plugging.

Low Martin

(agent)

Form CP-2/3

INVOICED
DATE 9-17-97
49036
9-8

110