

15.009.20671.0001

RECEIVED

9/1/98

COMMISSION

6-10 4-020053

JUN 18, 1998

API Number: 15-009-20,671X001

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

C NE _____ /4 SEC. 19, 20 S, 15 W
3960 _____ feet from S section line
1320 _____ feet from E section line

6-18-1998

Operator license# 3833

Lease: M. Smith Well # 1 OWWO

Operator: John H. Shaida

County: Barton 12818

Address: 4126 N. Sweet Bay Circle
Wichita, Kansas 67226

Well total depth 3944 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 1132 feet

Aband. oil well , Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Mike's Testing and Salvage, Inc. License# 31529

Address: P.O. Box 467 - Chase, Kansas 67524

Company to plug at: Hour: 10:00 A.M. Day: 10 Month: June Year: 1998

Plugging proposal received from: Mike Kelso

Company: Mike's Testing and Salvage, Inc. Phone: 316-636-2525

Were: Shot off 5 1/2" at 2000'. Perfs at 3875' - 3903'.
Ordered 270 sxs 60/40 pozmix - 10% gel and 400# hulls.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All , Part [], None []

Completed: Hour: 4:15 P.M., Day: 10, Month: June, Year: 1998

Actual plugging report: 8 5/8" set at 1132' w/375 sxs cement. 5 1/2" set at 3941' w/100 sxs cement. Sanded to 3825' and topped with 5 sxs cement with dump bailer. Shot casing off at 2000'. Pulled casing to 1950' - tied onto 5 1/2" - pumped 135 sxs 60/40 pozmix - 10% gel with 300# hulls. Pulled casing to 1175'. Pumped 40 sxs cement with 100# hulls. Pulled casing to 725' - pumped 35 sxs cement. Pulled casing to 200' - pumped 40 sxs cement. Circulated cement. P.O.O.H. casing. Cement at top of hole.

Remarks: Allied Cementing.

Condition of casing (in hole): GOOD BAD _____

Anhy. plug: YES NO _____

Bottom plug (in place): YES , CALC _____, NO _____

Dakota plug: YES , NO _____

Plugged through TUBING _____, CASING .

Elevation: 2107 GL

I did / did not observe the plugging.

Gay F. Fisher
(agent)

INVOICED

DATE JUN 18 1998

INV. NO. 50797