

6
030359

API NUMBER 15-009-23,810.0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NWNWNE SEC. 19, T. 20 S., R. 15 WE

4950 feet from X/SE section line

2310 feet from SE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8624

Lease Name SMITH Well # B-1

Operator: GENESIS OIL AND GAS INC.

County BARTON 126.75

Name & Address 1505 KSB&T BUILDING

Well Total Depth 3900 feet

WICHITA, KANSAS

Conductor Pipe: Size _____ feet

67202

Surface Casing: Size 8 5/8 feet 762 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor ALLEN DRUG. License Number 157

Address GREAT BEND, KANSAS

Company to plug at: Hour: PM Day: 12 Month: 12 Year: 19 84

Plugging proposal received from STEVE

(company name) ALLEN DRUG. (phone) _____

were: ORDER 140 SX. 50/50 PZ 6% GEL 3% - 1 8 5/8 WIPER PLUG. SPOT WITH D.P. WITH HEAVY MUD BETWEEN PLUGS.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:PM Day: 12 Month: 12 Year: 19 84

ACTUAL PLUGGING REPORT RAN D.P. TO 1130' AND DISPLACED 25 SX. CEMENT THRU

D.P. PULLED D.P. TO 760' AND DISPLACED 90 SX. CEMENT THRU D.P.

PULLED D.P. SET PLUG @ 40' WITH HULLS AND 10 SX. CEMENT TO BOTTOM

OF CELLAR. BLUE CEMENT CO. 15 SX. CEMENT CIRCULATED IN RATHOLE

ELEV. 2104 ANHY 1128-58. (RECEIVED) ALT. 1 COMPLETION.

STATE CORPORATION COMMISSION

Remarks: JAN 02 1985

(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

(did/did not) observe this plugging.

DATE 1-14-85

Signed Carl Goodrow
(TECHNICIAN)

INS. NO. 6418

Dec 28-84
3