

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-23230-00-00
Spot: W2NWNENW Sec/Twnshp/Rge: 19-20S-15W
4950 feet from S Section Line, 3640 feet from E Section Line
Lease/Unit Name: IANNITTI Well Number: 1
County: BARTON Total Vertical Depth: 3900 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: PO BOX 2757 202 SOUTH ST. FRANCIS
WICHITA, KS 67201

Conductor Pipe: Size _____ feet: 3 1/2 75
Surface Casing: Size 8.625 feet: 335 185 SX CMT
Production: Size 5.5 feet: 3897 150 SX CMT
Liner: Size _____ feet: _____

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/24/2002 11:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE INC
Proposal Rcvd. from: GARY REH Company: GORE OIL COMPANY Phone: (308) 345-1597

Proposed Plugging Method: Ordered out 200 sxs 60/40 pozmix - 10% gel - 18 sxs gel - 300# hulls.
Well had been squeezed to surface.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/24/2002 2:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded back to 3680'.
Perforated casing at 1725' and 1125'.
TIH with tubing to 3658' - tied onto and mixed 16 sxs gel,
followed by 50 sxs cement with 300# hulls and displaced to 3000'.
Pulled tubing up to 1767' and circulated cement with 130 sxs.
POOH and top staged with 10 sxs.
Max. P.S.I. 300#. S.I.P. 200#.

RECEIVED
JAN 31 2002
KCC WICHITA
1-31-2002

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

INVOICED Form CP-2/3

DATE Feb 1, 02

INV. NO. 2002061327

JAN 25 2002

GENESIS OIL & GAS
 301 S. TERRACE
 WICHITA, KS 67218
 CONTR WOODMAN-IANNITTI #1 IANNITTI
 CITY BARTON 19-20-15W 16³⁰
 330' FNL &
 1640' FWL, NW/4
 GEOL _____ FIELD PAWNEE ROCK
 ELV 2104 KB SPD 8/18/83 CARD ISSUED 3/22/84 IP P 60 BO & 10 BWPD
2099 GL ARB 3830-3831
 AP / 15-009-23,230

| | |
|---|---|
| + | + |
| + | + |
| + | + |
| + | + |

| DRLRS | Tops | Depth/Datum |
|-------|-------|-------------|
| ANH | | 1115+ 989 |
| B/ANH | | 1142+ .962 |
| ARB | | 3792-1688 |
| RTD | | 3900-1796 |

8 5/8 " 335 / 185SX; 5 1/2 " 3897 / 150SX
 DST (1) 3822-3840 (ARB) / 30-30-30-30, GTS / 20", GA 395
 MCFGPD DECR TO TSTM, REC 3150' FL, SIP 1107-1107#, FP
 255-367 / 459-649#, HP 2153-2093#, BHT 121"
 MICT - CO, PF (ARB) 3848-3849, W / 4 SPF, AC 250G (10% ACE-
 TIC), SWB DWN, NS, PF (ARB) 3830-3831, W / 4 SPF, AC 250G
 (10% ACETIC), SWB DWN, SQZ'D PFS W/10SX CMT, RE-PF (ARB)
 3830-31, W / 4 SPF, AC 250G (10% ACETIC), SWB DWN, SO,
 POP, P 60 BO & 10 BWPD (GR 38°), 9/28/83

COPYRIGHT 1983
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS