

6062000  
6 062000

API NUMBER 15- 009-22,902-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW, SEC. 26, T 20 S, R 15 W  
4290 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5161  
Operator: Palomino Petroleum  
Name & Address: R R 5 Box 51 C  
Newton, Ks. 67114

Lease Name Unruh C Well # 1  
County Barton 120.58  
Well Total Depth 3710 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 912

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering Inc. License Number 5111  
Address Box 698 Great Bend, Ks. 67530

Company to plug at: Hour: 9:30 AM Day: 27 Month: Nov Year: 19 89

Plugging proposal received from Jim Rockhold  
(company name) Rockhold Engineering Inc. (phone) 913-792-2506

were: Order 200 sks 60/40 poz 8% gel 5 sks hulls.

Plugging Proposal Received by Gilbert G. Scheck  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:15 PM Day: 27 Month: Nov Year: 19 89

ACTUAL PLUGGING REPORT 8 5/8" set at 912' w/425 sks. 5 1/2" set at 3710' w/125 sks.

Top perf at 3511'. Plugged bottom w/sand and 5 sks cement to 3475'. Shot pipe four times and recovered 2203'. Pumped in 8 5/8" 25 sks cement followed w/5 sks hulls in 175 sks cement w/ 650 psi.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 4 1990

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Halliburton  
(If additional description is necessary, use BACK of this form.)

INVOICED

(If applicable) observe this plugging.

DATE 1-5-90

Signed Gilbert G. Scheck  
(TECHNICIAN)

NO. 26914