

4-060881

S-15

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-009-24,074.0000

NW NW NW /4 SEC. 26, 20 S, 15 W  
4950 feet from S section line  
4950 feet from E section line

Operator license# 5663

Lease: Graber Well # 1

Operator: Hess Oil Company

County: Barton

Address: P.O. Box 1009  
McPherson, Kansas 67460

Well total depth 3765 <sup>122.34</sup> feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 10 3/4 Inch @ 534 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: P.O. Box 209 - Chase, Kansas 67524

Company to plug at: Hour: 11:00 A.M. Day: 15 Month: May Year: 1996

Plugging proposal received from: Mike Kelso/Manny

Company: Mike's Testing & Salvage, Inc. Phone: 316-938-2943

Were: Order 200 sxs 60/40 posmix - 4% gel.  
Order 300 sxs 60/40 posmix - 10% gel and hulls.  
Plug while pulling casing.  
Annulus behind production under artesian flow conditions.

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 30 1996

CONSERVATION DIVISION  
WICHITA, KS

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [ ], Part [ X ], None [ ]

Completed: Hour: 7:30 P.M., Day: 15, Month: May, Year: 1996

Actual plugging report: 10 3/4" to 534'. 7" to 3720' w/150 sxs. Perfs 3649' - 3663'.  
Sanded to 3600' and spotted 7 sxs cement with dump bailer. Tied onto annulus and pumped 200  
sxs 60/40 posmix - 4% gel to kill artesian flow. Shot casing at 1672'. Tied onto production  
casing and pumped 200 sxs 60/40 posmix - 10% gel with 400# hulls. Pulled braden head slips  
with hole condition stable. Pulled casing to 900' and loaded with 35 sxs cement. Pulled  
casing and topped with 35 sxs. Installed swedge and valve to control any problems. Tied  
onto surface casing on May 22, 1996, and pumped 25 sxs cement with hulls. Max. P.S.I. 800#.  
S.I.P. 800#.

Remarks: Allied Cementing.  
Condition of casing(in hole): GOOD  BAD  Anhy.plug: YES  NO   
Bottom plug(in place): YES , CALC , NO  Dakota plug: YES , NO   
Plugged through TUBING , CASING . Elevation: 1942 GL

Did [ ] observe the plugging.

(agent)

INVOICED

DATE JUN 05 1996

INV. NO. 45714

D/B