

11-18-87

To: 6 061373
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-009.23663.0000

NE NE SW, SEC. 25, T 20 S, R 15 (W/S)

2310 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5591

Lease Name B Smith Well # 1-25

Operator: Westech Energy Co. Inc.

County Barton 119.28

Name & Address Box 949

Well Total Depth 3670 feet

Great Bend, Ks. 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 870

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering Inc. License Number 5111

Address Box 698 Great Bend, Ks. 67530

Company to plug at: Hour: 10:00 AM Day: 18 Month: Nov Year: 19 87

Plugging proposal received from Jim Rockhold

(company name) Rockhold Engineering Inc. (phone) 316-792-2506

were: Order 100 sks 65/35 Poz 10% Gel 2% Econolite 5 sks Hulls.

Plugging Proposal Received by Gilbert G. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:20 PM Day: 18 Month: Nov Year: 19 87

ACTUAL PLUGGING REPORT Set at 870' w/450 sks. 5 1/2" set at 3669' w/125 sks.

Top perf at 3636'. Plugged bottom w/sand and 5 sks cement to 3580'. Shot pipe one and recovered 2788'. Pumped in 8 5/8" 5 sks Hulls. 100 sks cement w/700 Psi.

STATE CORPORATION COMMISSION

NOV 30 1987 11-30-1987

CONSERVATION DIVISION Wichita, Kansas

Remarks: By Allied. (If additional description is necessary, use BACK of this form.)

I do hereby observe this plugging.

Signed Gilbert G. Scheck (TECHNICIAN) Gilbert G. Scheck

DATE 12-7-87

INV. NO. 19153

1944

0301178

RECEIVED

APR 1944