

3-1

96

6 061792

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 009-23,473.0000

SE \_\_\_\_\_, SEC. 25, T 20 S, R 15 W/EX

2310 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5591

Lease Name Unruh Well #1-25

Operator: Westech Energy Co. Inc.

County Barton 119.76

Name & Address Box 949

Well Total Depth 3685 feet

Great Bend, Ks. 67530

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 869

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering Inc. License Number 5111

Address Box 698 Great Bend, Ks. 67530

Company to plug at: Hour: 11:30AM Day: 1 Month: March Year: 19 89

Plugging proposal received from Jim Rockhold

(company name) Rockhold Engineering Inc. (phone) 316-792-2506

were: \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION

MAR 21 1989 3-21-1989

CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Gilbert G. Scheck  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:15PM Day: 1 Month: Mar Year: 19 89

ACTUAL PLUGGING REPORT 8 5/8" set at 869' w/450 sks. 5 1/2" set at 3683' w/125 sks. Top perf at 3633'. Plugged bottom w/sand and 5 sks cement to 3600'.

Shot pipe one time and recovered 2800'. Pumped in 8 5/8" 25 sks cement followed w/5 sks Hulls in 175 sks cement w/300 psi.

Remarks: By Allied Ran line to 900'

(If additional description is necessary, use BACK of this form.)

INVOLVED

(If you observe this plugging.

DATE 3-23-89

Signed *Gilbert G. Scheck*  
(TECHNICIAN)

INV. NO. 24210

Gilbert G. Scheck