

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-009-23,978.0000

N2 NW SE /4 SEC. 25, 20 S, 15 W
2310 feet from S section line
1980 feet from E section line

Operator license# 5591

Lease: Unruh "B" Well # 1

Operator: Westech Energy Company, Inc

County: Barton

Address: P.O. Box 949
Great Bend, Kansas 67530

Well total depth 3690 feet ^{119.92}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8% Inch @ 870 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Great Bend Casing Pullers, Inc. License# 4635

Address: P.O. Box 251, Great Bend, Kansas 67530

Company to plug at: Hour: Day: 24 Month: September Year: 1993

Plugging proposal received from: Gary Burke

Company: Great Bend Casing Pullers, Inc. Phone: 316/793-911

Were: 8 1/2" surface casing set @ 870' w/425 sx cmt; 5 1/2" production casing set @ 3689' w/125 sx cmt; Elevation: 1913'; T.D.: 3690'; P.B.T.D.: 3683'; Anhydride: 861 - 885'; Salt Section: 1327 - 1652'; Dakota: Subcrops; Perforations: Arbuckle 3630 - 34';

Ordered 175 sx cmt 60/40 pozmix 8% gel w/1/2 # flowcel per sx and 8 sx gel

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 16:30, Day: 24, Month: September, Year: 1993

Actual plugging report: 9/20/93 - sanded off bottom and plugged bottom. w/5 sx cmt. 9/24/93 - shot off 5 1/2" casing @ 2713'; plugged through 5 1/2" casing; pulled to 1702'; displaced 35 sx cmt to 1600'; pulled to 910'; displaced 45 sx cmt to 800'; pulled to 692'; pumped 8 sx gel followed by a wiper plug; pulled to 325'; circ. cmt to surf w/90 sx cmt; pulled remaining casing; hole remained full of cmt.

RECEIVED
STATE CORPORATION COMMISSION
SEP 28 1993

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Allied performed the cementing
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: 1913 GL

I did[X] / did not[] observe the plugging.

[Signature]
(agent)

Form CP-2/3

INVOICED
OCT 05 1993

DATE
INV. NO. 38871

